



City of Bellevue
Development Services Department
Land Use Staff Report

Proposal Name: Silverado Memory Care

Proposal Address: 14341 SE 16th St

Proposal Description: Design Review and Critical Areas Land Use Permit approval and Conditional Use Permit recommendation for a 21 unit memory care facility located within a newly constructed building. The proposal includes a request to reduce a steep slope critical area buffer.


File Number: 18-126959-LB, 18-126958-LD 18-126964-LO

Applicant: Wattenberger Architects


Decisions Included: Combined Conditional Use Permit, Design Review, Critical Areas Land Use Permit and SEPA (Process II)

Planner: Leah Chulsky, Associate Planner

State Environmental Policy Act Threshold Determination: Determination of Non-Significance


Elizabeth Stead, Environmental Coordinator
Development Services Department

Director's Recommendation: **Approval with Conditions**
Michael A. Brennan, Director
Development Services Department

By: 
Elizabeth Stead

Application Date: October 8, 2018
Decision Publication Date: October 24, 2019
SEPA, Design Review and Critical Areas Appeal Deadline: November 7, 2019
Recommendation Publication Date: October 24, 2019
Conditional Use Hearing Date: November 14, 2019

For information on how to appeal the project, visit the Permit Center at City Hall or call (425) 452-6800. Appeal of the decision must be received in the City Clerk's office by 5 p.m. on the date noted for the appeal deadline.

I. REQUEST AND PROJECT DESCRIPTION

A. Background

The applicant is requesting Design Review, Critical Areas Land Use Permit approval, and a Threshold Decision under the State Environmental Policy Act (SEPA) to construct a 21 unit structure in which the Silverado Memory Care will operate. The subject site is 35,100 square feet in the Neighborhood Business (NB) land use district and within Single Family and Multifamily Transition Overlay Districts. The site contains a steep slope critical area totaling 1,494 square feet. The applicant is proposing to reduce the buffer from the top of slope from 50 feet to 10 feet and restore the existing slope and remaining buffer with native vegetation.

The applicant also requests a Conditional Use Permit (CUP) to operate a memory care community operated by Silverado Senior Living. The memory care facility is categorized as an assisted living use in the Land Use Code (LUC). Per the Residential Land Use Charts under LUC 20.10.440, assisted living facilities require Conditional Use Permit approval in the NB land use district.

Per LUC 20.25H.255 a Critical Areas Land Use Permit (CALUP) with a Critical Areas Report is required to modify a steep slope critical area buffer. The Critical Areas Report is intended to provide flexibility to sites with degraded critical area functions and values. The Critical Areas Report shall demonstrate the proposal with the requested modification leads to equivalent or better functions and values than what would result from application of the standard requirements that protect steep slopes, slope buffer, and the structure setback.

B. Review Process

Design Review and Critical Areas Land Use Permit, and SEPA Determination are all Process II decisions made by the Director of the Development Services Department. The process includes public noticing with a minimum 14-day comment period. The Director's decision shall be written in a staff report to indicate whether the application has been approved, approved with conditions, or denied. The decision will be publicly noticed with a mandatory 14-day appeal period. Process II decisions may be appealed by parties of record who submitted comments on the application. Any appeal submitted shall be heard at a public hearing before the City Hearing Examiner.

Per the Land Use Code, assisted living facilities such as Silverado Memory Care require a Conditional Use Permit which is a Process I decision (LUC 20.35.300). Process I decisions are quasi-judicial decisions made by the Hearing Examiner. Following the Directors recommendation, a public hearing will be held before the Hearing Examiner. Following the public hearing, the Hearing Examiner will issue a written report which will set forth a decision to approve, approve with modifications, or deny the application. The Hearing Examiners decision is appealable to the City Council.


C. Site Design

The proposed development will be accessed via a 26 foot driveway originating at SE 16th Street at the east side of the northern property line which will be the only

access to the site. Access to the proposed structure is a short driveway segment between the existing asphalt edge of SE 16th Street and the proposed basement garage. Stormwater runoff from the building and driveway will be collected and detained in a vault located under the building. Additional landscaping is proposed to buffer the proposed structure from the neighboring single family and multifamily neighborhoods. The vault will connect to the existing storm water system. There is 1,494 square feet of steep slope across the site running east to west. The proposal includes intensive perimeter landscaping and the retention of all significant trees within 15 feet from the property lines, and will set aside the area not impacted in the slope, buffer and structure setback as open space within Native Growth Protection Easement (NGPE) as mitigation for critical areas disturbance.

See Condition of Approval regarding NGPE in Section IX of this Report.

Site Plan



D. Building Design

In response to topography, the structure is sunken and partially recessed into the slope. The structure is pushed away from the adjacent single family neighborhood to allow for access and an increased vegetated buffer. The proposed structure will mimic northwest contemporary residences within the surrounding neighborhood containing stone, exposed timber, and hardie panels of beiges and green to help blend the structure naturally into the site and reduce visual impact. Limited entry is proposed at the primary entrance, and limited use of shed roofs help create a contemporary look for the project while still being in character with the neighborhood. The proposed structure is 27 feet-7 inches, (maximum height allowed is 35 feet). This height is consistent with and lower than the maximum height allowed within the adjacent residential neighborhood.



View Looking East from SE 16th Street



View Looking West from SE 16th Street

II. SITE DESCRIPTION, LAND USE CONTEXT ZONING AND CRITICAL AREAS

A. Site Description

This is a 35,100 square foot undeveloped site. The site is mostly square. The site slopes from east to west with 1,494 square feet of steep slope critical area and x square feet of top of slope buffer. The site contains 9 trees with a total of 206 diameter inches.



Aerial Photo/Site Context

B. Land Use Context and Zoning

The site has a Comprehensive Plan designation of Neighborhood Business (NB) and lies entirely within Single Family and Multifamily Transition Area Design Districts. Multifamily uses lie to the immediate south, single family lies to the immediate east and commercial to the north and west.



Zoning Map

C. Critical Areas

The project has steep slopes and stream critical areas on-site. The Land Use Code protects critical areas and their important functions and values:

i. Geologic Hazard Areas

Geologic hazards pose a threat to the health and safety of citizens when commercial, residential, or industrial development is inappropriately sited in areas of significant hazard. Some geologic hazards can be reduced or mitigated by engineering, design, or modified construction practices. When technology cannot

reduce risks to acceptable levels, building in geologically hazardous areas is best avoided (WAC 365-190).

Steep slopes may serve several other functions and possess other values for the City and its residents. Several of Bellevue's remaining large blocks of forest are located in steep slope areas, providing habitat for a variety of wildlife species and important linkages between habitat areas in the City. These steep slope areas also act as conduits for groundwater, which drains from hillsides to provide a water source for the City's wetlands and stream systems. Vegetated steep slopes also provide a visual amenity in the City, providing a "green" backdrop for urbanized areas enhancing property values and buffering urban development.

III. CONSISTENCY WITH LAND USE CODE REQUIREMENTS:

A. General Provisions of the Land Use Code

1. **Use**
 Uses are regulated by Sec. 20.10.440 (Use Charts). The assisted living use proposed for this project is permitted in the NB zone through a CUP.
2. **Dimensional Requirements**
 As conditioned, the proposal meets the dimensional requirements of the Land Use Code Section 20.20.010 and 20.25B Transition Area Design Districts.

Table 1 – Dimensional Requirements

BASIC INFORMATION	
Zoning District	Neighborhood Business
Site Area (Sqft)	35,100 square feet
Critical Area and Buffer (Sqft)	4,494 square feet
Buildable Area (Sqft)	30,606 square feet

	Permitted/Required	Proposed
Density	<p>15 units/acre per LUC 20.20.010</p> <p>(15 du/acre x 30,506 sq. ft. /acre) + (15 du/acre x 4494 sq. ft. /acre x .8 dev/factor) = 11 dwelling units</p> <p>*Per footnote (22) Density for senior citizen dwelling, congregate care senior house, and assisted living is calculated as follows: units less than 600 square feet count as one-half and units 600 square feet or greater count as one unit.</p>	<p>21 units under 600 sq. ft. counted as a .5 unit each (21 x .5 = 10.5) for a total of 10.5 units</p> <p>Meets LUC requirement</p>

Lot Coverage by Structure	35% of 30,606 SF = 10,7012 SF LUC 20.20.010	31% = 10,424 SF Meets LUC requirement
Impervious Surface	60% of 35,100 = 21,060 SF LUC 20.20.010	50% = 17,550 SF Meets LUC requirement
Setbacks	<u>NB in Single Family Transition Design District:</u> Front: 20 ft. Rear: 30 ft. Side: 30 ft. (eastern property line) LUC 20.20.010	Front: 20 ft. (north) Rear: 60 ft. (south) Side: 30 ft. (east) Meets LUC requirement
Building Height	NB: * 35 feet as measured from average <u>existing</u> grade LUC 20.010 Footnote (25) * The maximum height may be increased to 30 feet only if residential uses or administrative office uses are provided on the second floor, and provided the structure does not exceed two stories. Design shall meet the definition of story pursuant to the International Building Code, Section 202, as adopted and amended by the City of Bellevue. * Building height shall be measured from average existing grade around the building to the highest point of a flat roof or to the mean height between the tallest eave and tallest ridge of a pitched roof. All mechanical equipment and screening shall not exceed the maximum height permitted above.	27 feet- 7 inches The building is designed so that the lower level meets the building code definition of basement and is not considered a story above grade plane. This includes limiting the finished floor surface of the level above to no more than 12 feet above finished ground level at any point and not more than 6 feet above average grade plane. <u>See Condition of Approval regarding Building Height in Section IX of this Report.</u> Meets LUC requirement
Parking	Minimum = .5 x 21 units = 12 stalls. Maximum = 1.5 x 21 units = 31.5 stalls LUC 20.20.590	15 stalls Meets LUC requirement
Landscape Requirements	Street Frontage: 20 foot wide Type III landscaping Interior Property Line Abutting District Receiving Transition: 20 foot wide Transition Area Landscape	Street Frontage: 20' wide Type III landscaping Interior Property Line Abutting District Receiving Transition: 20 foot wide Type III

	<p>Buffer</p> <p>Interior Property Lines: 8 foot Type III landscaping (property lines not abutting a district receiving transition).</p> <p>LUC 20.20.520 and 20.25B.</p>	<p>Interior Property Lines (not abutting a district receiving transition): 8 foot Type III landscape buffer.</p> <p>Meets LUC requirement</p>
Tree Retention	<p>Site Perimeter: 100% tree retention</p> <p>Site Interior: 15% of 206 diameter inches = 30.9 diameter inches</p> <p>LUC 20.20.900 and 20.25B</p>	<p>All significant trees within 15 feet of all property lines will be retained.</p> <p>Site Interior: 170 diameter inches (85 percent)</p> <p>Meets LUC requirement</p>
Mechanical Equipment	<p>Locate on the roof or below grade and visually screen, unless this requirement is modified by the City for projects requiring discretionary approval per LUC 20.20.525.C.5 & 6.</p>	<p>All mechanical equipment will be located inside the buildings within the roof top mechanical wall.</p> <p>Meets LUC requirements</p>

3. Landscaping

a. Tree Retention

As approved, the proposal will retain all significant trees within 15 feet of all property lines. The proposal will also retain 85 percent or 170 diameter inches of the significant trees in the site interior (206 diameter inches). A significant number of the inches to be retained are located along the eastern property line. As conditioned, the applicant will provide tree retention in excess of that which is required to help maintain the existing wooded character and provide for a vegetated buffer between the proposed development and the existing single family neighborhood both on the interior and perimeter of the site.

See Condition of Approval regarding Landscape Plan in Section IX of this Report.

b. Perimeter Landscaping

i. Street Frontage

A 20 foot Type III landscape buffer will be planted along the entire street frontage property line (SE 16th Street). A design that includes the following: extensive native landscaping along the northern property line (80% of the proposed plants are native) with trees and shrubs and additional landscaping throughout the site that includes a mix of evergreen and deciduous material. In addition, the applicant has worked

with the City of Bellevue to increase the amount of trees onsite and planting significant native trees, shrubs and groundcover.

There is an existing irrigation water meter and controller for Right of Way irrigation along SE 16th Street provided by the City. Any other irrigation for landscaping on private property must be on a separate, private service line. Applicant is required to protect all existing lateral lines, main lines, sleeving, wiring and components until inspection by Parks irrigation staff before moving forward with planned modifications. Any disruption of existing irrigation function must be short duration as it supplies other streetscape areas along SE 16th Street. Damage is to be reported immediately to the construction inspector for the project.

All irrigation in the ROW shall be schedule 40 pipe, using a spray system. No drip irrigation allowed in the planting strip. Applicant shall provide a 6 inch sleeve for irrigation under all driveway crossings and a 4 inch sleeve under sidewalk crossings. Irrigation laterals in the Right of Way should be minimum 1 inch.

See Condition of Approval regarding Landscape Plan, Maintenance and Right of Way Street Scape in Section IX of this Report.

ii. Interior Property Lines Abutting Less Intense District

The applicant is proposing 20-foot landscape buffer along the eastern property line which abuts the R-5 zoning district and along the southern property line abutting mutli-family which are both receiving the transition. The approved landscape buffer shall contain additional plantings to include a minimum of 5 trees per 1,000 square feet of buffer and include shrubs and ground cover (no more than 40 percent of the trees are to be deciduous). The approved buffer meets the Transition Area Landscape Buffer requirements.

See Condition of Approval regarding Landscape Plan in Section IX of this Report.

4. Transition Area Design Guidelines (LUC 20.25B)

A. Site Design Guidelines

i. Vehicular Access

Whenever possible, vehicular access should be designed so that traffic is not directed through an abutting residential district of lower intensity.

Response: Access to the development will be from a single point of entry off of SE 16th Street. No additional access will be directed through the residential neighborhood.

ii. **Loading and Refuse Collection**

Loading and refuse collection areas should be on the side of a building facing away from an abutting residential district of lower intensity, but not in a front yard setback.

Response: Garbage and recycling will be located within the garage with sufficient space to allow for truck turn around. The applicant has coordinated with Republic Services to verify turn around space and overhead clearance for rear loading trucks.

See Condition of Approval regarding Loading and Refuse Collection in Section IX of this Report.

iii. **Tree Retention**

In addition to the minimum requirements of LUC 20.20.520, site development should maximize the retention of existing significant vegetation in order to soften the visual impact on adjacent residential uses.

Response: The applicant proposes to retain all significant trees within 15 feet all property lines. The site interior contains 206 diameter inches of significant trees. The applicant is proposing to retain 170 diameter inches or 85 percent. As conditioned, the proposal includes significant trees, shrubs and ground cover while maintaining the existing vegetated buffer between the subject site and the neighboring multifamily and multifamily neighborhoods.

vi. **Contextual Compatibility**

Surrounding vegetation, topography, street patterns, parking configuration and building massing should be considered in order to result in a compatible fit between the proposed development and existing residential development.

Response: The proposed building massing, orientation of the pedestrian and vehicular access off of SE 16th Street and architectural detailing of the facades are all single family residential in character. The buildings are designed to fit not only into the single family and multifamily neighborhoods around the proposal site but to also minimize massing by sinking the structure into the slope. The proposed structure will mimic northwest contemporary residences within the surrounding neighborhood and exterior materials will include

stone, exposed timber, and hardie panels of beiges and green to help blend the structure naturally into the site and reduce visual impact to surrounding properties. Limited entry at the primary entrance, and limited use of shed roofs help create a more contemporary look without being out of character for the neighborhood. The proposed structure is approved at 27 feet-7 inches, this height is consistent with, and lower than the maximum height allowed within the adjacent residential neighborhood.

B. Building Design Guidelines

i. Exterior Surfaces

Building surfaces facing abutting residential districts should be clad with materials which are similar to or compatible with surrounding uses, and which minimize reflected lights.

Response: The exterior surfaces are similar and in certain applications superior, to those found in the residential surrounding neighborhood. They include stone, exposed beams, hardie panels, and earth-toned colors. None of the materials are reflective.

ii. Building Façade

Building facades should incorporate elements such as stepbacks, offsets, angled facets, deep roof overhangs, recesses and other architectural features which serve to break down the scale. The larger the building, the greater the number and variety of such elements that may be necessary to achieve the effect of diminishing scale.

Response: The applicant has used architectural modulation and detailing to create interest and break down the scale of the building. The applicant has limited the use of shed roof to provide a more contemporary façade in line with some of the exiting new residences in the area.

iii. Roof Form

Pitched roof forms are preferred in order to enhance the compatibility with nearby residential areas. However, under certain circumstances, a stepped roof form could achieve a similar effect.

Response: The pitched roof enhances the compatibility with the nearby residential areas. All mechanical units will be served by through wall PTAC's. The corridors, service, and amenity spaces will be served by a centrally located HVAC system. The equipment is intended to be placed in an approximately 20 foot x 26 foot rooftop equipment well. The 35 foot height limit with bonus is the midpoint of a sloped roof,

or top of parapet or flat roof. The final height of the screening parapet will be adjusted when we have more developed mechanical plans. As currently designed, the structure has anticipated a 2 foot 6 inch flat truss at that location, with a 6 foot 8 inch screening parapet on top of that. Given the 35 foot height limit, the parapet could be adjusted to a maximum height of 8 feet 6 inches and meet the requirement.

See Condition of Approval regarding height in Section IX of this Report.

iv. Communication Dishes

Communication dishes greater than one meter in diameter should not be visible from adjacent residential districts.

Response: No communication dishes greater than one meter in diameter are proposed for this project.

See Condition of Approval regarding Rooftop Equipment in Section IX of this Report.

v. Exterior Materials and Colors

Materials and colors used on the building facades should be compatible with nearby residential buildings and the surrounding natural environment; however, colors and materials used for the purpose of accent may be approved.

Response: The applicant proposes beige and green hardie panel siding along with stone and exposed lumber to be compatible with surrounding residential structures and to blend into the vegetated site; thereby reducing the overall visual impact of the proposal.

5. CRITICAL AREAS REQUIREMENTS LUC 20.25H

Critical Areas Impacts

The site is 35,100 square feet with 4,494 square feet of critical slope and associated top-of-slope buffer. The applicant is proposing the following permanent and temporary impacts through a Critical Areas Report.

- 456 square feet of permanent impact to steep slopes
- 720 square feet of permanent impact to slope buffer and setback
- 780 square feet of total temporary impact to steep slopes, buffer, and setback on the site and within the City right-of-way.
- Removal of 2 significant trees

Conformance with Critical Areas Performance Standards

The City of Bellevue Land Use Code Critical Areas Overlay District (LUC 20.25H) establishes performance standards and procedures that apply to development on any site which contains in whole or in part any portion designated as steep slope critical area, buffer, or structure setback through a critical area report process. The applicant has prepared the following information related to critical areas on-site:

- **Geotechnical Engineering Report by Associated Earth Sciences dated April 9, 2018**
- **Critical Areas Report and Habitat Assessment by The Wetland Resources dated September 24, 2018**

The project elements are subject to the requirements found in LUC 20.25H as specified below:

Performance Standards – Landslide hazards and steep slopes (LUC 20.25H.125) In addition to generally applicable performance standards set forth in LUC 20.25H.055 and 20.25H.065, development within a landslide hazard or steep slope critical area or the critical area buffers of such hazards shall incorporate the following additional performance standards in design of the development, as applicable. The requirement for long-term slope stability shall exclude designs that require regular and periodic maintenance to maintain their level of function.

- A.** Structures and improvements shall minimize alterations to the natural contour of the slope, and foundations shall be tiered where possible to conform to existing topography;

Response: The structure will include a basement parking garage daylighting to the east with two residential stories above the ground surface. Direct impact to the buffer will be limited to construction of the entrance driveway. By constructing the building in this way, the size of the driveway is reduced and thus limiting the overall impact to the steep slope.

- B.** Structures and improvements shall be located to preserve the most critical portion of the site and its natural landforms and vegetation;

Response: The driveway design minimizes the size of impact and therefore preserves the maximum amount of steep slope and vegetation. The retaining wall and added vegetation will further assist in stabilizing the slope. The remainder of the development has been mindful of the site conditions by deepening foundations to create parking and thereby minimizing the building footprint to avoid further impacts to the steep slope area.

- C. The proposed development shall not result in greater risk or a need for increased buffers on neighboring properties;

Response: The proposed development minimizes the risk to neighboring properties. The location of the building on the west side of the site allows for over 90 feet of vegetation between the proposed building and the east property line (down slope). This site design approach reduces the risk of potential erosion problems affecting adjacent properties. By maintaining existing vegetation in the steep slope along with installing mitigation plantings, this project will not increase the risk of instability of the slope adjacent to the building. By deepening the foundations for basement construction of the main structure and entry retaining walls, there will not be increased loads on the slopes, thus eliminating a greater risk or need for increased buffers. A retaining wall along the southern facing portion of the driveway will also reduce impacts to the steep slope in this area. The geotechnical report also states that the site is not considered a landslide hazard area due to the dense to very dense glacial till geology of the area that makes up the slope.

- D. The use of retaining walls that allow the maintenance of existing natural slope area is preferred over graded artificial slopes where graded slopes would result in increased disturbance as compared to use of retaining wall;

Response: The use of a retaining wall will be confined to the entrance driveway to avoid further grading into the steep slope and buffer. After retaining wall installation, the area behind will be planted per the approved mitigation plan. No grading or artificial slopes are proposed in the critical areas.

See Condition of Approval regarding Mitigation Plan in Section IX of this Report.

- E. Development shall be designed to minimize impervious surfaces within the critical area and critical area buffer;

Response: The proposed development minimizes impervious surface within the critical area and buffer by placing the building parallel to the western property line away from the critical area. In addition, where critical area is disturbed for driveway, the path that has been clearly defined with walls and the width is the minimum necessary to accommodate the required traffic, reducing the need for a more substantial access driveway.

- F. Where change outside the building footprint is necessary, the site retention system should be stepped and regrading should be designed to minimize topographic modifications. On slopes in excess of 40

percent, grading for yard area may be disallowed where inconsistent with this criteria;

Response: The change in grade within the disturbed area has been clearly defined within the driveway corridor. The walls are located so there will be minimal disturbance. Stepping the walls within the driveway location would involve further disturbance and topographic modification.

- G. Building foundation walls shall be utilized as retaining walls rather than rockeries or retaining structures built separately and away from the building whenever feasible. Freestanding retaining devices are only permitted when they cannot be designed as structural elements of the building foundation;

Response: The proposed retaining wall along the driveway will join the basement garage foundation walls. The remaining portion of the driveway retaining wall that is freestanding is away from the building but will provide the required access to the below grade structure.

- H. On slopes in excess of 40 percent, use of pole-type construction which conforms to the existing topography is required where feasible. If pole-type construction is not technically feasible, the structure must be tiered to conform to the existing topography and to minimize topographic modification;

Response: Pole-type construction of the driveway is not technically feasible. The retaining wall varies in height to conform to the topography. Tiered construction of the retaining wall is not feasible and will create further disturbance.

- I. On slopes in excess of 40 percent, piled deck support structures are required where feasible for parking garages over fill-based construction types; and

Response: The parking garage will be underground and cut into the lot with the associated driveway entrance cut into the slope. No construction will be occurring within the steep slope.

- J. Areas of new permanent disturbance and all areas of temporary disturbance shall be mitigated and/or restored pursuant to a mitigation and restoration plan meeting the requirements of LUC 20.25H.210.

Response: The applicant has provided a mitigation plan (see Attachment 1). As conditioned, the plan meets the requirements of LUC 20.25H.210. As conditioned, the proposal will set aside the remainder of the slope, buffer and structure setback as open space within Native Growth Protection Easement (NGPE) as mitigation for critical areas disturbance.

See Condition of Approval regarding Mitigation Plan and NGPE in Section IX of this report.

Performance Standards – Landslide hazards and steep slopes

(LUC 20.25H.145) Modifications to geologic hazard critical areas and critical area buffers shall only be approved if the Director determines that the modification:

- A. Will not increase the threat of the geological hazard to adjacent properties over conditions that would exist if the provisions of this part were not modified;

Response: Associated Earth Sciences Inc., (AESI), in a report dated April 9, 2018 (in file) analyzed the site and concluded the site contains only one steep slope with no landslide hazard. The project design mitigates for potential landslide risks from critical area impacts by retaining the majority of vegetation in the slope area, additional plantings, and placement of a retaining wall along the driveway to minimize the disturbance of the steep slope area. The slope on-site is underlain by dense glacial soils making it less prone to seismic liquefaction.

- B. Will not adversely impact other critical areas;

Response: This project will not adversely impact other critical areas as none were found immediately adjacent to the site. The slope is found only on the subject site.

- C. Is designed so that the hazard to the project is eliminated or mitigated to a level equal to or less than would exist if the provisions of this part were not modified;

Response: The proposed driveway will be reinforced with a retaining wall and the surrounding slope will be stabilized with mitigation planting. The development as approved will not increase the hazard risk to less than what would exist if the hazard was not modified.

- D. Is certified as safe as designed and under anticipated conditions by a qualified engineer or geologist, licensed in the state of Washington;

Response: A Geotechnical Engineer for AESI provided recommendations within their report dated April 9, 2018. These recommendations shall be included within further grading and building permits.

See Condition of Approval regarding Geotechnical Recommendations and Inspection in Section IX of this report.

- E. The applicant provides a geotechnical report prepared by a qualified professional demonstrating that modification of the critical area or

critical area buffer will have no adverse impacts on stability of any adjacent slopes and will not impact stability of any existing structures. Geotechnical reporting standards shall comply with requirements developed by the Director in City of Bellevue Submittal Requirements Sheet 25, Geotechnical Report and Stability Analysis Requirements, now or as hereafter amended;

Response: A Geotechnical Engineer for AESI provided recommendations within AES's report dated April 9, 2018. These recommendations shall be included within further grading and building permits.

See Condition of Approval regarding Geotechnical Recommendations and Inspection in Section IX of this report.

- F. Any modification complies with recommendations of the geotechnical support with respect to best management practices, construction techniques or other recommendations; and

Response: A Geotechnical Engineer for AESI provided recommendations within AES's report dated April 9, 2018. These recommendations shall be included within further grading and building permits.

See Condition of Approval regarding Geotechnical Recommendations and Inspection in Section IX of this report.

- G. The proposed modification to the critical area or critical area buffer with any associated mitigation does not significantly impact habitat associated with species of local importance, or such habitat that could reasonably be expected to exist during the anticipated life of the development proposal if the area were regulated under this part. (Ord. 5680, 6-26-06, § 3)

Response: A detailed discussion of existing conditions and analysis of the proposed development can be found in Section 4.0 "Habitat Assessment" of the Critical Areas Report (in file). To summarize, no habitat specifically associated with species of local importance was found. Therefore, no direct or indirect impacts are proposed to any habitats associated with species of local importance.

IV. PUBLIC NOTICE

The City initially notified the public of this proposal on January 17, 2019 with mailed notice and publication in the Weekly Permit Bulletin. One, double-sided public information sign was also installed at the site entrance on the same day. In addition, a public meeting was held January 23, 2019 at Bellevue City Hall. No members of the community attended.

V. SUMMARY OF TECHNICAL REVIEWS

A. Utilities

Surface Water

The Silverado project has proposed under building detention to control runoff from the site. The detention system can be feasibly constructed to provide runoff control for the project. The system will connect into the public storm drainage system located within SE 16th Street. Storm drainage impacts to the site will require the project to meet thresholds for Department of Ecology minimum requirements 1-9. The site exceeds thresholds for minimum requirements 1, 2, 4, 5, 7 and 9. The applicant has proposed detention to mitigate minimum requirement 7 and cannot feasibly implement minimum requirement 5 because of steep slopes on the site except for amended soils in landscape areas. Minimum requirement 4 for the historic flow path will be maintained with the proposed drainage system. Minimum requirement 1 has been met with the preparation of a stormwater site plan. Minimum requirement 2 will be covered under a clearing and grading permit. Connection to the public storm water system will be made in SE 16th Street.

Water

Water is available to the site in SE 16th Street from an 8 inch water main. The applicant has proposed to connect water meters and fire lines off this main. There is adequate capacity in the existing 8 inch water main in SE 16th Street to provide the project domestic, irrigation and fire flow water.

Sewer

Sewer is available to the site from an 8 inch sewer main in SE 16th Street. The applicant has proposed to install a new sewer stub, and manhole for connection to the sewer main located in SE 16th Street. which has adequate capacity to serve the site with sewer service.

See Condition of Approval regarding Conceptual Utilities Approval in Section IX of this Report.

B. Transportation

Project Summary

The proposed Silverado Memory Care site is located on the south side of SE 16th Street east of 45th Place SE and West of 144th Avenue SE, shaded in blue below.



The existing site is vacant. The Silverado Bellevue project proposes to construct a two story building over one level of basement parking. The proposed Memory Care facility with 21 units is estimated to generate 9 p.m. peak hour trips.

Multimodal Site Access

Vehicle Access and Loading

The existing site currently has no vehicular access. The proposed vehicular access to and from the project site will be provided via a new 26 foot commercial driveway approach onto SE 16th Street approximately 50 feet from the east property line. The proposed access will support all vehicular access including deliveries and garbage to be accommodated on-site without backing onto the public street. On-street loading will not be allowed or permitted. Truck turning movements for the garbage truck were verified with AutoTurn diagrams.

Pedestrian Access

The existing pedestrian access is provided to the site through the sidewalk along SE 16th Street on the north side of the site. The existing sidewalk is approximately 6 feet wide adjacent to the roadway.

The proposed development is required to construct a minimum 8 foot wide sidewalk, and a minimum 5 foot wide landscape planter between the back of curb and the sidewalk enhancing pedestrian safety with separation from the roadway.

Near the west property line, an existing Puget Sound Energy (PSE) above ground vault is located within the path of the proposed sidewalk. The existing PSE vault will remain in place, and the proposed project will meander the sidewalk to the south of the PSE vault maintaining the minimum 8 foot wide sidewalk.

Bicycle Access

Existing bicycle facilities on SE 16th Street. are provided by an approximately 5 foot bicycle lane in the eastbound and westbound directions. No new bicycle

infrastructure is listed in Bellevue's plans within the vicinity of the site. No new bicycle infrastructure will be constructed with this project.

Transit Service Access

King County Metro operates service in the vicinity of the site. The nearest transit stop is provided on 145th Place SE approximately 400 feet west of the project site (south of SE 16th Street.). The service provides access to King County Metro Transit routes 245 and 271. The stop can be reached from the site using the existing sidewalk.

Sight Distance for Vehicles and Pedestrians

Sight distance for vehicles at the proposed driveway onto SE 16th Street was evaluated. The right setback line to the east is shown to meet the City's standards. The sight distance assessment is documented in the Transportation Impact Study.

The left setback line to the West is shown less than the required sight distance. The proposed driveway is located on a tangent section of a horizontal curve to the west.

It is also located on a tangent section of a vertical crest curve to the west, at the same location of the horizontal curve, and a vertical sag curve to the east. Due to the site topography, roadway vertical curves and the horizontal curve, the available sight distance is less than the required sight distance. The driveway location was evaluated, and it was placed at the location providing the maximum available sight distance from the site. A design justification will be completed for the project for deviation from the standards.

Sight distance for pedestrians at the proposed driveways is required to meet the City's horizontal and vertical standards and will be evaluated during the plan review to ensure that any proposed landscaping, signage, walls, handrails and street furnishings are placed to avoid obstruction within the sight lines for pedestrians.

Street Lighting

Street lighting photometric calculations were evaluated by the applicant along SE 16th Street. New street light poles and replacement of existing luminaires with new LED fixtures will be required to meet the City's current light level standards.

Transportation Infrastructure

To provide safe pedestrian and vehicular access in the vicinity of the site, and to provide infrastructure improvements with a consistent and attractive appearance, the construction of street frontage improvements is required as a condition of development approval. The design of the improvements must conform to the requirements of the Americans with Disabilities Act, the Transportation Development Code (BCC 14.60), and the provisions of the Transportation Department Design Manual.

Engineering and construction details must be shown on the civil engineering plans submitted as part of the clearing and grading permit. The engineering plans shall be the controlling document on the design of these features; architectural and landscape plans must conform to the engineering plans. During construction, city inspectors may require additional survey work at any time to confirm proper elevations. The building grade and elevations shall be consistent with the curb and sidewalk grade shown in the approved civil engineering plans.

See Conditions of Approval relating to Civil Engineering Plans – Transportation Plans – Transportation, Building and Site Plans – in Section IX of this Report

For the Silverado Memory Care development project, the transportation infrastructure will include a new driveway approach, curb and gutter, planter strip, and sidewalk on the SE 16th Street frontage of the site.

Prior to any form of occupancy, completion of the following transportation infrastructure is required:

1. Construct new minimum 26 foot wide commercial driveway approach for site access onto SE 16th Street at the location required to maximize the sight distance. An approved Design Justification is required prior to completion of the project.
2. Construct new standard concrete curb and gutter along the development frontage to replace the existing concrete curb and gutter.
3. Construct new planter strip along the development frontage with a minimum width of 5 feet.
4. Construct new sidewalk along the development frontage with a minimum width of 8 feet.
5. The planter strip shall have spray irrigation, root barrier, street trees and landscaping.
6. Install street lighting per Bellevue Standards; including new poles, arms, and fixtures as needed to meet Bellevue's minimum photometric values.
7. Install City fiber communication vaults, junction boxes, conduits and wiring per City's requirements.
8. Any proposed landscaping, signage, and street furnishings shall be placed to avoid obstruction within the sight lines for vehicles and pedestrians.
9. All landscape planters shall have irrigation from a private metered water source unless the City has agreed to accept a new meter or provide water from an existing City meter.
10. A combined street tree and street light plan is required for review and approval prior to completion of engineering and landscape plans. The goal is to provide the optimum number of street trees while not compromising the light and safety provided by streetlights. Street trees and streetlights must be shown on the same plan sheet with the proper separation (generally 25 ft. apart) and the proper spacing from driveways (ten feet from Point A in standard drawing SW-140-1 or equivalent).
11. The Americans with Disabilities Act (ADA) requires that sidewalk cross slopes not exceed two percent. The sidewalk cross slope may be less than two percent only if the sidewalk has a longitudinal slope sufficient to provide adequate drainage. Bellevue's standard for curb height is six inches,

except where curb ramps are needed. The engineering plans must comply with these requirements, and must show adequate details, including spot elevations, to confirm compliance. New curb and sidewalk shall be constructed in compliance with these requirements. Building elevations shall be consistent with the required curb and sidewalk elevations. Spot elevations must be included in the building plans in a manner that proves that building elevations are designed to correspond to the sidewalk elevations shown in the engineering plans, especially at entrances and other key points. Curb and sidewalk elevations will not be revised to fit the building, and city inspectors may require spot surveys during construction in order to confirm the required elevations.

12. ADA also requires provision of a safe travel path for visually handicapped pedestrians. Potential tripping hazards are not allowed in the main pathway. Any planter boxes installed in the sidewalk to improve pedestrian sight distance at driveways must be designed to reduce the tripping potential and must not extend more than two feet into the public sidewalk. Traffic signal controller boxes and streetlight contactor cabinets must be located so as not to interfere with the main pedestrian path. Buildings shall be designed so that doors do not swing out into the pedestrian path. Installation of colored or textured bands to guide pedestrians in the direction of travel is advisable, subject to the requirements for non-standard sidewalk features. ADA-compliant curb ramps shall be installed where needed, consistent with City and Washington State Department of Transportation (WSDOT) standard drawings. If such standards cannot be met, then deviation from standards must be justified on a Design Justification Form to be filed with the City of Bellevue Transportation Department.
13. The new landscaping planter strip within the sidewalk along the public road shall be irrigated with a private metered water source. Electrical connections for lighting in planter strips may be allowed, if installed in compliance with the electrical code and subjected to an electrical inspection. Irrigation devices and electrical components shall not create a tripping hazard in the sidewalk. Installation of the proposed planter shall include a spray irrigation system, soil preparation, root barrier and plantings. Root barrier and soil preparation are described in Standard Drawing SW-130-1. Landscaping in the right-of-way shall be maintained by the abutting property owner(s) unless maintenance has been accepted by the city.
14. The design and appearance of the sidewalk and landscaping shall comply with the standards and drawings in the Transportation Department Design Manual. The sidewalk shall be constructed of standard concrete with a broom finish and a 2 ft. by 2 ft. score pattern, unless both the Transportation Department and the Development Services Department agree to accept any non-standard pattern, color, or other features.
15. Any non-standard features or vegetation shall not create a sight obstruction within any required sight triangle, shall not create a tripping or slipping hazard in the sidewalk, and shall not create a raised fixed object in the street's clear zone. The materials and installation methods must meet typical construction requirements.
16. To the extent feasible, no new utility vaults that serve only one development

will be allowed within a public sidewalk. Vaults serving a broader public purpose may be located within a public sidewalk. To the extent feasible, no utility vaults may be located within the primary walking path in any sidewalk.

17. No fixed objects, including fire hydrants, trees, and streetlight poles, are allowed within ten feet of a driveway edge, defined as Point A in standard drawing SW-140-1 or equivalent. Fixed objects are defined as anything with breakaway characteristics greater than a four-inch by four-inch wooden post.
18. No new overhead utility lines will be allowed within or across any right of way or sidewalk easement, and existing overhead lines must be relocated underground.

See Conditions of Approval regarding Transportation Infrastructure and Street Development Requirements and Street Frontage Improvements in Section IX of the Report.

Easements

The applicant shall provide sidewalk and utility easements to the City as needed to encompass the full required width of any sidewalks along SE 16th Street.

The applicant shall provide easements to the City for location of signal, street light, and fiber facilities consisting of above-grade boxes and/or below-grade vaults between the building and sidewalk within the landscape area on the frontage. Transformers and utility vaults to serve the building shall be placed inside the building or below grade, to the extent feasible.

See Conditions of Approval regarding Existing Easements, Easements for Signal Control, Street Light Boxes, Vaults and Sidewalk/Utility Easements in Section IX of this Report.

Use of the Right-of-Way (ROW) During Construction

Applicants often request use of the right of way and of pedestrian easements for materials storage, construction trailers, hauling routes, fencing, barricades, loading and unloading and other temporary uses as well as for construction of utilities and street improvements. A Right of Way Use Permit for such activities must be acquired prior to issuance of any construction permit including demolition permit. Sidewalks may not be closed except as specifically allowed by a Right of Way Use Permit.

See Condition of Approval regarding Right of Way Use Permit in Section IX of this Report.

Pavement Restoration

The City of Bellevue has established the Trench Restoration Program to provide developers with guidance as to the extent of resurfacing required when a street has been damaged by trenching or other activities. Under the Trench Restoration Program, every street in the City of Bellevue has been examined and placed in one of three categories based on the street's condition and the period of time since it has last been resurfaced. These three categories are, "No Street Cuts

Permitted,” “Overlay Required”, and “Standard Trench Restoration.” Each category has different trench restoration requirements associated with it. Damage to the street can be mitigated by placing an asphalt overlay well beyond the limits of the trench walls to produce a more durable surface without the unsightly piecemeal look that often comes with small strip patching.

Near the development site, SE 16th Street is classified as Grind and Overlay required. Should street cuts prove unavoidable or if the street surface is damaged in the construction process, a half-street or full-street (depending on the extent of street cuts or damage) grind and overlay will be required for a minimum of 50 ft.

See Condition of Approval regarding Pavement Restoration in Section IX of this Report.

C. Fire

The Bellevue Fire Department Fire Prevention Division has reviewed the submittal in accordance with the 2015 International Fire Code, 2015 International Building Code, City of Bellevue requirements, and good fire protection practices. This review was based upon, and limited to, the information presented on drawings and/or materials received in our office. The Fire Department has reviewed this application. The proposal generally conforms to the Fire Code requirements for site circulation and access. Final review and approval will occur through the associated building permits for this proposal. As conditioned, Fire staff found no issues with the proposed development.

See Conditions of Approval regarding Site Circulation, Sprinkler Requirements and Alarm Systems, Carbon Monoxide Alarms, Key-Box Access and Extinguishing Systems in Section IX of this report.

D. Clear and Grade

The Clearing and Grading Division of the Development Services Department has reviewed the proposed development for compliance with Clearing and Grading codes and standards. As conditioned, Clearing and Grading staff found no issues with the proposed development.

See Conditions of Approval regarding Geotechnical Review and Inspection, Storm Water Pollution and Rainy Season Restrictions in Section IX of this Report.

VI. STATE ENVIRONMENTAL POLICY ACT (SEPA)

Environmental review is required for the proposal under the State Environmental Policy Act (SEPA), Chapter 43.21C RCW and Washington Administrative Code (WAC) 197-11, and the City’s Environmental Procedures Code, Chapter 22.02 of the Bellevue City Code (BCC). The Environmental Checklist together with information provided below (and in the official file) adequately discloses expected environmental impacts associated with the proposed Design Review approval. The environmental review indicates no probability of significant adverse environmental impacts occurring as a result of the proposal. The Environmental Checklist submitted with the application adequately discloses expected

environmental impacts associated with the project. City codes and requirements, including the Clear and Grade Code, Utility Code, Land Use Code, Noise Ordinance, Building Code and other construction codes adequately mitigate expected environmental impacts. Therefore, issuance of a Determination of Non-Significance is the appropriate threshold determination under the State Environmental Policy Act requirements.

Adverse impacts which are less than significant are usually subject to City Codes or Standards which are intended to mitigate those impacts. Where such impacts and regulatory items correspond, further documentation is not necessary. For other adverse impacts which are less than significant, Bellevue City Code Sec. 22.02.140 provides substantive authority to mitigate impacts disclosed through the environmental review process.

A. EARTH AND WATER

The submitted geotechnical reports by Associated Earth Sciences found a surficial layer of duff, root mat and organic rich topsoil which ranged from three to three and a half feet thick. Immediately below the surficial duff and topsoil exists silty sand with gravel which is interpreted to be lodgment till. The geotechnical engineer found no seepage of ground water on-site and there are no water features on the site. The project will be required to comply with all erosion and sediment control BMPs and the Clearing and Grading code requirements as part of future development permits.

B PLANTS AND ANIMALS

Construction will require removal of 23 significant trees as discussed in this report. The area outside of the developed footprint and parking lot is proposed to be restored with vegetation per the submitted mitigation plan and landscaping plan. As noted, the landscaping plan is required to be incorporated into the mitigation plan and include all native vegetation.

C. TRANSPORTATION

Long Term Impacts and Mitigation

The City has prepared a traffic forecasting model for the 2030 horizon year to assess cumulative impacts that may result from growth and development during that period. This modeling analysis is based on a projected land use scenario and improvements to the transportation system that would occur during this time period.

Under the level of service standard detailed in the Transportation Code, the City is divided into 14 Mobility Management Areas (MMAs), each with an area average standard and a congestion management standard. The traffic modeling shows that all of the MMAs would meet both standards. This project proposes to add a net increase of 21 dwelling units of Assisted Living in MMA 9, East Bellevue. This level of development is within the assumptions of the City's traffic modeling and does not require additional mitigation.

In addition, traffic impact fees are used by the City to fund street improvement projects to alleviate traffic congestion caused by the cumulative impacts of development throughout the City. Payment of the transportation impact fee, as required by Chapter 22.16 BCC, contributes to the financing of transportation improvement projects in the current adopted Transportation Facilities Plan, and is considered to be adequate mitigation of long-term traffic impacts. Fee payment is required at the time of building permit issuance. Impact fees are subject to change and the fee schedule in effect at the time of building permit issuance will apply.

See Condition of Approval regarding Impact Fees in Section IX of this Report.

Mid-Range Impacts and Mitigation

Project impacts anticipated to occur in the next six years are assessed through a concurrency analysis. The Traffic Standards Code (BCC 14.10) requires that development proposals generating 30 or more new p.m. peak hour trips undergo a traffic impact analysis to determine if the concurrency requirements of the State Growth Management Act are maintained.

The Silverado Bellevue development will generate 9 new p.m. peak hour trips; therefore, concurrency is not required for this project.

Short Term Operational Impacts and Mitigation

A traffic impact analysis (TIA) memorandum dated September 6, 2019, was prepared for this project by TENW. The TIA included assessment of the forecasted trip generation, site access, sight distance for vehicles and pedestrian, and truck turning movements. With 9 new p.m. peak hour trips, no short-term traffic impacts are expected, and no additional traffic mitigation is required. Frontage improvements are required on SE 16th Street, which will include the installation of new sidewalk and planter strip to improve pedestrian access to the development.

D. Noise

Exterior Noise

As conditioned, short term impacts related to noise generation as a result of the construction will be minimized. Normal hours for allowed generation of noise related to construction are from 7:00 am to 6:00 pm Monday through Friday and 9:00 am to 6 pm on Saturday. Exceptions to the construction noise hour limitation contained in the Noise Control Code MAY NOT be granted pursuant to 9.18.020C.1 & 2. However, prolonged exposure to noise created by extended hour construction activity is likely to have a significant impact of inhabitants of surrounding commercial and residential properties during the proposed timeline for construction. If expanded hours are necessary to accommodate a specific component of construction, a noise permit shall be required for exemption from the Noise Control Code must be submitted in advance of the scheduled onset of extended hour construction activity. In accordance with Bellevue City Code – BCC

9.10 Noise Control, the City will only be providing construction noise exemptions for the following work:

- Work in the ROW and essential public facilities (i.e., Water connections that require a main shut off are required to be done at night by the Utility Dept., public school construction)
- Work to accommodate transportation mitigation
- Required evening haul routes

Work that has been previously determined by sound level monitoring to not exceed the maximum permissible noise levels. Utility/site work on private projects/property is not essential public facilities.

See Condition of Approval regarding Noise in Section IX of this Report.

Interior Noise Levels

The Bellevue City Code, BCC 9.18 limits interior noise levels within residential structures to 40 dBa in sleeping areas and 45 dBa in non-sleeping areas. Special construction is generally necessary to meet these thresholds. Prior to the issuance of any occupancy permits, the applicant shall verify that this threshold has been met.

See Condition of Approval regarding Interior Noise in Section IX of this Report.

VI. CHANGES TO THE PROPOSAL RESULTING FROM CITY REVIEW

A. Transportation

During Predevelopment Services review, the applicant was required to move the proposed driveway to its existing location within the slope. This location is required based on Transportation site distance and performance standards. No other location was feasible.

VII. DECISION CRITERIA

A. Design Review:

The Director may approve, or approve with modifications, an application for Design Review if the proposal fulfills the Design Review Decision Criteria in LUC 20.30.F.145:

1. The proposal is consistent with the Comprehensive Plan.

The project is consistent with the Comprehensive Plan's Urban Design Element. The proposed development supports the following Subarea and Comprehensive Plan Policies:

Comprehensive Plan

The site is designated NB (Neighborhood Business) in the Comprehensive Plan and lies within the Single Family and Multifamily Residential Transition

Area Design Districts in the Southeast Bellevue Subarea of the Bellevue Comprehensive Plan.

Southeast Bellevue Subarea Policies:

Policy S-SE-2: Enhance or improve the existing residential character through landscaping, building orientation, and building design for all new development and physical improvements.

Policy S-SE-7: Expand uses in neighborhood commercial districts to better serve the needs of surrounding neighborhoods by allowing for a variety of retail, office, and residential uses; provided that the character and level of development is of a low intensity which is compatible with the adjacent residential districts.

Response: The site is zoned NB within the Southeast Bellevue Subarea of the Comprehensive Plan. The proposal will also utilize the existing vegetation and maintain an increased vegetated buffer between the proposed development and the existing single family neighborhood.

The proposed development will be limited to senior housing and will result in a lower impact than if the site were to be developed as fully commercial and will help bridge the existing single family neighborhood to the east with the commercially zoned to the west. The approved structure will be residential in both design and site development to mimic the surrounding neighborhood.

Housing Policies:

Policy HO-19: Support housing options, programs, and services that allow seniors to stay in their homes or neighborhood. Promote awareness of Universal Design improvements that increase housing accessibility.

Policy HO-20: Encourage a range of housing types for seniors affordable at a variety of income levels.

Response: The site is underutilized as an undeveloped lot in the NB land use district. The proposed development is surrounded by existing multifamily, commercial and single family development. The proposed use and design is compatible with the design of the surrounding built environment while providing additional housing options for seniors.

2. The proposal complies with the applicable requirements of this Code.

As conditioned, the proposal complies with applicable requirements of the Land Use Code as discussed in Section III of this report.

3. The proposal addresses all applicable design guidelines or criteria of this Code in a manner which fulfills their purpose and intent.

As conditioned, the proposal complies with the Development Standards (LUC 20.25B.040) and Design Guidelines for development in a Transition Area Design District (LUC 20.25B.050). Refer to Section III of this report for how the proposal has met the Development Standards.

4. The proposal is compatible with, and responds to, the existing or intended character, appearance, and quality of development and physical characteristics of the subject property and immediate vicinity.

By creating structures that are sunk into the natural slope and screened with increased vegetation the buildings will appear smaller in scale from the neighboring single family neighborhood. With the application of rich architectural detail, the proposed building is compatible with the surrounding neighborhood and will fit well within the greater single family and multifamily residential context.

5. The proposal will be served by adequate public facilities including streets, fire protection, and utilities.

All required public services and facilities are available to the site. The site has direct access to a major arterial (SE 16th St) which has capacity to carry the additional traffic expected to be attributed to the proposal (Traffic Study in project file). City water and sewer services are available to the site. The new driveway will provide fire truck access to the site.

B. Critical Areas Report – Decision Criteria (LUC 20.25H.255):

Decision Criteria – Proposals to Reduce Regulated Critical Area Buffer. The Director may approve, or approve with modifications, a proposal to reduce the regulated critical area buffer on a site where the applicant demonstrates:

1. The proposal includes plans for restoration of degraded critical area or critical area buffer functions which demonstrate a net gain in overall critical area or critical area buffer functions;

The applicant submitted a geotechnical report prepared by AESI which concludes that the steep slope is generally stable and adequate for the proposed development. The report states that the potential for slides is negligible provided the recommendations of the reports dated April 9, 2018 are followed during site clearing and construction. The applicant also submitted a Critical Areas Report dated September 24, 2018 which assessed impacts to the slope, habitat and buffer areas.

The proposed mitigation will improve water quality, hydrology, and slope stability functions of the on-site critical areas. The existing invasive plants on the site will be removed and replaced with native vegetation which will have better aerial coverage and root systems to protect slopes and intercept water. The vegetation will also improve habitat quality over what is existing onsite. .

2. The proposal includes plans for restoration of degraded critical area or critical area buffer functions which demonstrate a net gain in the most important critical area or critical area buffer functions to the ecosystem in which they exist;

The goal of the proposed mitigation is to improve overall habitat function over what is existing onsite, primarily through removal of invasive and noxious species and replanting with appropriate native species. The applicant will be required to restore all areas of temporary disturbance and will be restoring the modified buffer and structure setback back with a three tiered mitigation plan which will result in a net gain over existing conditions.

See Condition of Approval regarding Mitigation Plantings in Section IX of this Report.

3. The proposal includes a net gain in stormwater quality function by the critical area buffer or by elements of the development proposal outside of the reduced regulated critical area buffer;

All storm water from surfaces will be directed into collection systems. The vegetation remaining on the site will be enhanced through mitigation planting that will increase vegetation cover and quality that will improve storm water functions.

4. Adequate resources to ensure completion of any required restoration, mitigation and monitoring efforts;

Maintenance and monitoring is required for five years and is included as part of the critical areas report. A separate maintenance and monitoring plan will be required to be submitted as part of the clearing and grading permit for the project. An installation and assurance device will be required prior to clearing and grading permit issuance and a maintenance assurance device required prior to occupancy approval of the building that will be held for the five-year maintenance period. The amounts of the devices will be based on cost estimates for installation and monitoring provided at clearing and grading permit submittal. Copies of the monitoring reports will be submitted annually to the City

See Condition of Approval regarding Maintenance Device in Section IX of this Report.

5. The modifications and performance standards included in the proposal are not detrimental to the functions and values of critical area and critical area buffers off-site; and

There are no off-site critical area and critical area buffers. As discussed in Section III of this report, the applicable performance standards of LUC Section 20.25H are being met. The proposed mitigation will improve the functions of the steep slope on the site by removing invasive species and replanting to increase coverage by trees, shrubs, and ground cover. The proposed mitigation will improve habitat and slope stability functions.

6. The resulting development is compatible with other uses and development in the same land use district. (Ord. 5680, 6-26-06, § 3)

The proposed development is compatible with the surrounding multifamily, residential and commercial land use districts. The proposal is also compatible with the adjacent single family neighborhood and it meets the Transition Area requirements of LUC 20.25B and also provides an increased vegetated buffer between the existing single family homes and the proposed development

C. Critical Areas Land Use Permit – Decision Criteria (LUC 20.30P.140):

The Director may approve, or approve with modifications, an application for a Critical Areas Land Use permit if:

1. The proposal obtains all other permits required by the Land Use Code; and

The proposal will be required to obtain all application building permits prior to construction. Plans submitted for the development permits must reflect the plans reviewed under this approval.

See Condition of Approval regarding Building Permits in Section IX of this Report.

2. The proposal utilizes to the maximum extent possible the best available construction, design and development techniques which result in the least impact on the critical areas and critical area buffer; and

The project shall be constructed and inspected by the Engineer of Record to verify implementation of the recommended procedures and practices in the geotechnical report found in the reports prepared by prepared by AESI, on April 9, 2018. A report verifying implementation of inspection shall be submitted to Leah Chulsky prior to receipt of Temporary Certificate of Occupancy.

See Condition of Approval regarding Geotechnical Review and Inspection in Section IX of this Report.

3. The proposal incorporates the performance standards of Part 20.25H LUC to the maximum extent applicable; and

The proposal, as approved meets all applicable performance standards of Part 20.25H LUC. See Section III of this report for discussion.

4. The proposal is served by adequate public facilities including streets, fire protection, and utilities; and

All required public services and facilities are available to the site. The site has direct access to a major arterial (SE 16th Street) which has capacity to carry the additional traffic expected to be attributed to the proposal (Traffic Study in project file). City water and sewer services are available to the site. The new driveway

will provide fire truck access to the site.

5. The proposal includes a mitigation or restoration plan consistent with the requirements of LUC 20.25H.210; except that a proposal to modify or remove vegetation pursuant to an approved Vegetation Management Plan under LUC 20.25H.055.C.3.i; and

The proposal includes a mitigation plan that meets the requirements of LUC 20.25H.210. A final mitigation plan must be included with all subsequent construction permit applications. An installation and maintenance surety is required and the proposed planting will be monitored for 5 years.

See Condition of Approval regarding Mitigation Planting and Maintenance in Section IX of this Report.

6. The proposal complies with other applicable requirements of this code.

As discussed in this report, the proposal complies with all other applicable requirements of the Land Use Code. The proposal complies with all other applicable code requirements as approved or conditioned. Per LUC 20.30P.170, the applicant is required to provide hold harmless agreement prior to construction permit issuance.

See Condition of Approval regarding Hold Harmless Agreement in Section IX of this Report.

D. Conditional Use Permit – Decision Criteria (LUC 20.30B.140):

The Director may approve, or approve with modifications an application for Conditional Use Permit if:

1. The conditional use is consistent with the Comprehensive Plan.

The proposed development supports the following Subarea and Comprehensive Plan Policies:

Comprehensive Plan

The site is designated NB and lies within the Southeast Bellevue subarea of the Bellevue Comprehensive Plan. The Comprehensive Plan designation for this property is NB.

Land Use Element:

Policy LU-14: Protect residential areas from the impacts of nonresidential uses of a scale not appropriate to the neighborhood

Policy LU-19: Support mixed residential/commercial development in all Neighborhood Business and Community Business land use districts in a manner that is compatible with nearby uses.

Southeast Bellevue Subarea Policies:

Policy S-SE-2: Enhance or improve the existing residential character through landscaping, building orientation, and building design for all new development and physical improvements.

Policy S-SE-7: Expand uses in neighborhood commercial districts to better serve the needs of surrounding neighborhoods by allowing for a variety of retail, office, and residential uses; provided that the character and level of development is of a low intensity which is compatible with the adjacent residential districts.

Response: The site is zoned NB within the Southeast Bellevue Subarea of the Comprehensive Plan. The proposal will also utilize the existing vegetation and maintain an increased vegetated buffer between the proposed development and the existing single family neighborhood.

The proposed development will be limited to senior housing and will result in a lower impact than if the site were to be developed as full commercial and will help bridge the existing single family neighborhood to the east with the commercially zoned to the west. The approved structure will be residential in both design and site development to mimic the surrounding neighborhood.

2. The design is compatible with and responds to the existing or intended character, appearance, quality of development and physical characteristics of the subject property and immediate vicinity.

The proposed building massing, orientation of the pedestrian and vehicular access off of SE 16th Street and architectural detailing of the facades are all single family residential in character. The buildings are designed to fit not only into the single family and multifamily neighborhoods around the proposal site but to also minimize massing by sinking the structure into the slope. The proposed structure will mimic northwest contemporary residences within the surrounding neighborhood containing stone, exposed timber, and hardie panels of beiges and greens to help blend the structure naturally into the site and reduce visual impact. Limited storefront at the primary entrance, and limited use of shed roofs help create a more contemporary look without being out of character for the neighborhood. The proposed structure is at 27 feet- 7 inches is consistent with and lower than the maximum height allowed within the adjacent residential neighborhood.

3. The conditional use will be served by adequate public facilities including public streets, fire protection and utilities.

All required public services and facilities are available to the site. The site has direct access to a major arterial (SE 16th Street) which has capacity to carry the additional traffic expected to be attributed to the proposal (Traffic Study in project file). City water and sewer services are available to the site. The new driveway will provide fire truck access to the site.

4. The conditional use will not be materially detrimental to uses or property in the immediate vicinity of the subject property.

The proposed development will be limited to senior housing and will result in a lower impact than if the site were to be developed as fully commercial and will help bridge the existing single family neighborhood to the east with the commercially zoned to the west. The approved structure will be residential in both design and site development to mimic the surrounding neighborhood and will not be materially detrimental to uses or property in the surrounding vicinity.

5. The conditional use complies with the applicable requirements of the Land Use Code.

As conditioned the Conditional Use complies with all applicable Land Use Code requirements as discussed in Section III above. Per LUC 20.20.440 footnote (4), for senior housing, an agreement must be recorded with the King County Recorder's Office, or its successor agency, and filed with the Bellevue City Clerk, restricting senior citizen dwellings, congregate care senior housing, or assisted living to remain for the life of the project.

See Condition of Approval regarding Senior Housing Agreement in Section IX of this Report.

VIII. DECISION

After conducting the various administrative reviews associated with the proposal, including applicable Land Use consistency and City Code & Standard compliance reviews, the Development Services Department Director does hereby **APPROVE WITH CONDITIONS** the Design Review and Critical Areas Land Use Permit approvals for Silverado Memory Care Proposal. **Approval of these Permits does not constitute a permit for construction. A building permit, clear and grade permit, and/or utility permit is required and all plans are subject to review for compliance with applicable City of Bellevue codes and standards.**

Note- Expiration of Approval: In accordance with LUC 20.30P.150 a Critical Areas Land Use Permit automatically expires and is void if the applicant fails to file for a building permit or other necessary development permits within one year of the effective date of the approval.

Note - Vested Status of Design Review Approval: The vested status of the Design Review approval shall expire two years from the date of the City's final decision, unless a completed building permit application is filed before the end of the two year term. Upon issuance of a building permit, the vested status of a land use permit approval shall be automatically extended for the life of the project.

After conducting the various administrative reviews associated with this proposal, including Land Use consistency and City Code and Standard compliance reviews, the Director of the Development Services Department does hereby **RECOMMEND APPROVAL WITH CONDITIONS** of the Conditional Use Permit for the Silverado Memory Care Facility.

Note - Vested Status of CUP Approval: The vested status of the CUP approval shall expire two years from the date of the City's final decision, unless a completed building

permit application is filed before the end of the two year term. Upon issuance of a building permit, the vested status of a land use permit approval shall be automatically extended for the life of the project.

IX. CONDITIONS OF APPROVAL:

The following conditions are imposed under authority referenced:

Compliance with Bellevue City Codes and Ordinances

The applicant shall comply with all applicable Bellevue City Codes, Standards, and Ordinances, including but not limited to:

Applicable Ordinances	Contact Person
Clearing and Grading Code- BCC 23.76	Savina Uzunow, 425-452-7860
Construction Codes- BCC Title 23	Nate Tilson, 425-452-6866
Fire Code- BCC 23.11	Glen Albright, 425-452-4270
Land Use Code- BCC Title 20	Leah Chulsky, 425-452-6834
Noise Control- BCC 9.18	Leah Chulsky, 425-452-6834
Sign Code- BCC Title 22B	Leah Chulsky, 425-452-6834
Transportation Code- BCC 14.60	Randa Kiakos, 425-452-2569
Right of Way Use Code- BCC 14.30	Tim Stever, 425-452-4294
Utility Code- BCC Title 24	Mark Dewey, 425-452-6179

A. GENERAL CONDITIONS: The following conditions apply to all phases of development.

1. Utilities Conceptual Approval

Utility Department approval of the design review application is based on the final conceptual design submitted with this application. Final utility design and construction approval is not given under this permit. Small changes to the site layout may be required to accommodate the utilities after utility engineering is approved. The water, sewer, and storm drainage systems shall be designed per the current City of Bellevue Utility Codes and Utility Engineering Standards. A Utility Developer extension agreement will be required as a condition of this permit. Utilities Department design review, plan approval, and field inspection is performed under the Utility Developer Extension Agreement (UE). All connection charges will be due with the Developer Extension Agreement prior to issuance of the permit. Water, sewer and storm easements will be required as needed.

AUTHORITY: Bellevue City Code Title 24.02, 24.04, 24.06
REVIEWER: Mark Dewey, Utilities Department

2. Building Permit

Approval of this application does not constitute an approval of a development permit. A building permit and any other associated development permits are required. Plans submitted as part of any permit application shall be consistent with the activity permitted under this approval.

AUTHORITY: Land Use Code 20.30P.140
REVIEWER: Leah Chulsky, Development Services Department

3. Approved Modification

This decision approves the slope buffer modification as identified in the project site plans to construct a new structure with mitigation (refer to Attachment 1). This approval does not allow future structures or improvements to be located without future review and permits.

AUTHORITY: Land Use Code 20.30P.140
REVIEWER: Leah Chulsky, Development Services Department

4. Building Height

The maximum height may be increased to 35 feet only if residential uses or administrative office uses are provided on the second floor, and provided the structure does not exceed two stories and meets the requirements of LUC 20.25B.040.2 for allowed height bonus. Design shall meet the definition of story pursuant to the International Building Code, Section 202, as adopted and amended by the City of Bellevue.

The building is designed so that the lowest level meets the building code definition of basement and is not considered a story above grade plane. This includes limiting the finished floor surface of the level above to no more than 12 feet above finished ground level at any point and not more than 6 feet above average existing? grade plane.

Building height shall be measured from average existing grade around the building to the highest point of a flat roof or to the mean height between the tallest eave and tallest ridge of a pitched roof. All mechanical equipment and screening shall not exceed the maximum height permitted above.

AUTHORITY: Land Use Code 20.20.010 Footnote (25)
REVIEWER: Leah Chulsky, Development Services Department

B. PRIOR TO CLEARING & GRADING PERMIT ISSUANCE:

1. Right-of-Way Use Permit

Prior to issuance of any construction or clearing and grading permit, the applicant shall secure applicable right-of-way use permits from the City's Transportation Department, which may include:

- a) Designated truck hauling routes.
- b) Truck loading/unloading activities.
- c) Location of construction fences.
- d) Hours of construction and hauling.
- e) Requirements for leasing of right of way or pedestrian easements.
- f) Provisions for street sweeping, excavation and construction.
- g) Location of construction signing and pedestrian detour routes.
- h) All other construction activities as they affect the public street system.

In addition, the applicant shall submit for review and approval a plan for providing pedestrian access during construction of this project. Access shall be provided at all times during the construction process, except when specific construction activities such as shoring, foundation work, and construction of frontage improvements prevent access. General materials storage and contractor convenience are not reasons for preventing access.

The applicant shall secure sufficient off-street parking for construction workers before the issuance of a clearing and grading, building, a foundation or demolition permit.

AUTHORITY: Bellevue City Code 11.70 & 14.30
REVIEWER: Tim Stever, Transportation Department

2. Civil Engineering Plans – Transportation

Civil engineering plans produced by a qualified engineer must be approved by the Transportation Department prior to issuance of the clearing and grading permit. The design of all street frontage improvements and driveway accesses must be in conformance with the requirements of the Americans with Disabilities Act, the Transportation Development Code, the provisions of the Transportation Department Design Manual, and specific requirements stated elsewhere in this document.

All proposed infrastructure improvements within the right-of-way shall conform to current WSDOT Standard Specifications for Road, Bridge and Municipal Construction and to the City of Bellevue Special Provisions (BSP's).

All relevant standard drawings from the Transportation Department Design Manual shall be copied exactly into the final engineering plans. Requirements for the engineering plans include, but are not limited to:

- a) Traffic signs and markings.
- b) Curb, gutter, sidewalk, intersection, and driveway approach design. The engineering plans shall be the controlling document on the design of these features; architectural and landscape plans must conform to the engineering plans as needed.
- c) Curb ramps, crosswalk revisions, and crosswalk equipment such as pushbuttons.
- d) Installation or relocation of streetlights and related equipment.

- e) Undergrounding of existing overhead utility lines, which should be coordinated with adjacent sites. Transformers and utility vaults to serve the building shall be placed inside the building or below grade, to the extent feasible.
- f) As part of the traffic signal installation or modifications, the developer must pay a fee to integrate this signal into the city's adaptive signal management system (SCATS). Payment for SCATS is needed at the time the signal is added to the adaptive signal management system and in no case later than occupancy of the first building.
- g) Sight distance. Show the required sight triangles and include any sight obstructions, including those off-site. Sight distance triangles must be shown at all driveway locations and must consider all fixed objects and mature landscape vegetation. Vertical as well as horizontal line of sight must be considered when checking for sight distance.
- h) Driveway landings on sloping approaches must meet the requirements for commercial development.
- i) Trench restoration within any right of way or access easement.

Construction of all street and street frontage improvements must be completed prior to closing the clear and grade permit and right of way use permit for this project. A Design Justification Form must be provided to the Transportation Department for any aspect of any pedestrian route adjacent to or across any street that cannot feasibly be made to comply with ADA standards. Design Justification Forms must be provided prior to approval of the clear and grade plans for any deviations from standards that are known in advance. Forms provided in advance may need to be updated prior to project completion. For any deviations from standards that are not known in advance, Forms must be provided prior to project completion.

AUTHORITY: Bellevue City Code 14.60; Transportation Department Design Manual; Americans with Disabilities Act
REVIEWER: Randa Kiriakos, Transportation Department

3. Final Landscape and Irrigation Plan

The Final Landscape and Irrigation Plans shall be submitted with the building permit application to ensure compliance with all Land Use Code requirements.

Any sleeves for irrigation mainlines shall be placed within the project property lines.

The applicant shall record a copy of the approved project drawings, including the landscape and irrigation plans, and conditions of this Design Review with the King County Division of Records and Elections and with the Bellevue City Clerk.

The location of the refuse area shall be located within the individual garages and be taken out for pick up day only and then returned to the individual garages.

AUTHORITY: Land Use Code 20.20.520, 20.20.900.G and 20.25B.040.C
REVIEWER: Leah Chulsky, Development Services Department

4. Pesticides, Insecticides, and Fertilizers

The applicant must submit as part of the required Clearing and Grading Permit information regarding the use of pesticides, insecticides, and fertilizers in accordance with the City of Bellevue's "Environmental Best Management Practices".

AUTHORITY: Land Use Code 20.25H.220.H
REVIEWER: Leah Chulsky, Development Services Department

5. Existing Easements

Any utility easements contained on this site which are affected by this development must be identified. Any negative impact that this development has on those easements must be mitigated or easements relinquished.

AUTHORITY: Bellevue City Code 14.60.100
REVIEWER: Randa Kiriakos, Transportation Department

6. Easements for Signal Control and Street Light Boxes and Vaults

The applicant shall provide easements to the City for location of signal and street light facilities such as above-grade boxes and below-grade vaults between the building and sidewalk within the landscape area.

AUTHORITY: Bellevue City Code 14.60.100
REVIEWER: Randa Kiriakos, Transportation Department

7. Sidewalk/Utility Easements

The applicant shall provide sidewalk and utility easements to the City such that sidewalks outside of the City right of way along the property frontage are located within a pedestrian easement area.

AUTHORITY: Bellevue City Code 14.60.100
REVIEWER: Randa Kiriakos, Transportation Department

8. Geotechnical Review

The project geotechnical engineer must review the final construction plans, including all retaining walls and foundation designs. A letter from the geotechnical engineer stating that the plans conform to the recommendations in the geotechnical report and any addendums and supplements must be submitted to the clearing and grading section prior to issuance of the construction permit.

AUTHORITY: Clearing & Grading Code 23.76.050
REVIEWER: Savina Uzunow, Development Services Department, Clear & Grading Section

9. Final Mitigation Planting Area

The reduced geologic hazard critical area requires planting to mitigate the approved structure setback reduction in accordance with the project mitigation plan. **The applicant shall submit a final planting plan as part of the clear and grade permit which is consistent with the requirements in this report.**

AUTHORITY: Land Use Code 20.25H.220
REVIEWER: Leah Chulsky, Development Services Department

10. Maintenance and Monitoring

The planting area shall be maintained and monitored for 5 years as required by LUC 20.25H.220. A maintenance surety for the mitigation planting is required based on 150 percent of the cost estimate for all costs associated with maintenance and monitoring for 5 years of monitoring, maintenance activity, plant replacement, contingencies. The amount of the surety is determined by a cost estimate submitted as part of the clearing and grading permit. The maintenance surety is required prior final inspection of the clearing and grading permit. Photos from selected photo points will be included in the monitoring reports to document the planting. Annual monitoring reports are to be submitted to the Development Services Department Land Use Division at the end of the growing season by no later than November 30 for each year monitored. The reports, along with a copy of the planting plan, can be sent to Leah Chulsky at lechulsky@bellevuewa.gov or to the address below:

Development Services Department
City of Bellevue
PO Box 90012
Bellevue, WA 98009-9012

AUTHORITY: Land Use Code 20.30P.140; 20.25H.220
REVIEWER: Leah Chulsky, Development Services Department

11. Installation Device

To ensure the required mitigation and restoration of areas of temporary disturbance is completed, the applicant shall post an Installation Assurance Device prior to the building permit or clearing and grading permit issuance. The device shall be equal to 150% of the value of the approved mitigation. The device will be released when the applicant demonstrates required mitigation has successfully been installed.

AUTHORITY: Land Use Code 20.25H.125.J, 20.25H.220, and 20.40.490
REVIEWER: Leah Chulsky, Development Services Department

12. Hold Harmless Agreement

The applicant shall submit a hold harmless agreement in a form approved by the City Attorney which releases the City from liability for any damage arising from the location of improvements within a critical area structure setback in accordance with LUC 20.30P.170. The hold harmless agreement is required to be recorded with King County prior to building permit issuance. Staff will provide the applicant with the hold harmless form.

AUTHORITY: Land Use Code 20.30P.170
REVIEWER: Leah Chulsky, Development Services Department

13. Rainy Season Restrictions

Due to steep slopes on the site, no clearing and grading activity may occur during the rainy season, which is defined as October 1 through April 30 without written authorization of the Development Services Department. Should approval be granted for work during the rainy season, increased erosion and sedimentation measures, representing the best available technology must be implemented prior to beginning or resuming site work.

AUTHORITY: Bellevue City Code 23.76.093.A,
REVIEWER: Savina Uzunow, Development Services Department

14. Storm Water Pollution Prevention Plan

To ensure contaminated stormwater or construction-related runoff does not pollute adjacent surface water; a construction stormwater pollution prevention plan (CSWPPP) is required. The CSWPPP outline should be generally consistent with the SWPPP requirements of the National Pollutant Discharge Elimination System (NPDES) General Storm water Permit for Construction Activities.

AUTHORITY: Bellevue City Code 23.76.
REVIEWER: Savina Uzunow, Development Services Department

15. Transportation Infrastructure and Street Development Requirements

The final design of transportation infrastructure improvements shall be approved by the Transportation Department, including all construction of streets, street lighting, planter strips, sidewalks, signals, channelization, pedestrian paths and trails, and bicycle facilities according to the street design standards.

Prior to any form of occupancy, completion of the following transportation infrastructure is required:

1. Construct new minimum 26 ft. wide commercial driveway approach for site access onto SE 16th Street at the location required to maximize the sight distance. An approved Design Justification is required prior to completion of the project.

2. Construct new standard concrete curb and gutter along the development frontage to replace the existing concrete curb and gutter.
3. Construct new planter strip along the development frontage with a minimum width of 5 ft.
4. Construct new sidewalk along the development frontage with a minimum width of 8 ft.
5. The planter strip shall have spray irrigation, root barrier, street trees and landscaping.
6. Install street lighting per Bellevue Standards; including new poles, arms, and fixtures as needed to meet Bellevue's minimum photometric values.
7. Install City fiber communication vaults, junction boxes, conduits and wiring per City's requirements.
8. Any proposed landscaping, signage, and street furnishings shall be placed to avoid obstruction within the sight lines for vehicles and pedestrians.
9. All landscape planters shall have irrigation from a private metered water source unless the City has agreed to accept a new meter or provide water from an existing City meter.
10. A combined street tree and street light plan is required for review and approval prior to completion of engineering and landscape plans. The goal is to provide the optimum number of street trees while not compromising the light and safety provided by streetlights. Street trees and streetlights must be shown on the same plan sheet with the proper separation (generally 25 ft. apart) and the proper spacing from driveways (10 ft. from Point A in standard drawing SW-140-1 or equivalent).
11. The Americans with Disabilities Act (ADA) requires that sidewalk cross slopes not exceed two percent. The sidewalk cross slope may be less than two percent only if the sidewalk has a longitudinal slope sufficient to provide adequate drainage. Bellevue's standard for curb height is 6 in., except where curb ramps are needed. The engineering plans must comply with these requirements, and must show adequate details, including spot elevations, to confirm compliance. New curb and sidewalk shall be constructed in compliance with these requirements. Building elevations shall be consistent with the required curb and sidewalk elevations. Spot elevations must be included in the building plans in a manner that proves that building elevations are designed to correspond to the sidewalk elevations shown in the engineering plans, especially at entrances and other key points. Curb and sidewalk elevations will not be revised to fit the building, and city inspectors may require spot surveys during construction in order to confirm the required elevations.
12. ADA also requires provision of a safe travel path for visually handicapped pedestrians. Potential tripping hazards are not allowed in the main pathway. Any planter boxes installed in the sidewalk to improve pedestrian sight distance at driveways must be designed to reduce the tripping potential and must not extend more than two feet into the public sidewalk. Traffic signal controller boxes and streetlight contactor cabinets must be located so as not to interfere with the main pedestrian path. Buildings shall be designed so that doors do not swing out into the pedestrian path. Installation of colored or textured bands to guide pedestrians in the direction of travel is advisable, subject to the requirements for non-standard sidewalk features. ADA-compliant curb ramps shall be installed where

needed, consistent with City and WSDOT standard drawings. If such standards cannot be met, then deviation from standards must be justified on a Design Justification Form to be filed with the Transportation Department.

13. The new landscaping planter strip within the sidewalk along the public road shall be irrigated with a private metered water source. Electrical connections for lighting in planter strips may be allowed, if installed in compliance with the electrical code and subjected to an electrical inspection. Irrigation devices and electrical components shall not create a tripping hazard in the sidewalk. Installation of the proposed planter shall include a spray irrigation system, soil preparation, root barrier and plantings. Root barrier and soil preparation are described in Standard Drawing SW-130-1. Landscaping in the right-of-way shall be maintained by the abutting property owner(s) unless maintenance has been accepted by the city.
14. The design and appearance of the sidewalk and landscaping shall comply with the standards and drawings in the Transportation Department Design Manual. The sidewalk shall be constructed of standard concrete with a broom finish and a 2 ft. by 2 ft. score pattern, unless both the Transportation Department and the Development Services Department agree to accept any non-standard pattern, color, or other features.
15. Any non-standard features or vegetation shall not create a sight obstruction within any required sight triangle, shall not create a tripping or slipping hazard in the sidewalk, and shall not create a raised fixed object in the street's clear zone. The materials and installation methods must meet typical construction requirements.
16. To the extent feasible, no new utility vaults that serve only one development will be allowed within a public sidewalk. Vaults serving a broader public purpose may be located within a public sidewalk. To the extent feasible, no utility vaults may be located within the primary walking path in any sidewalk.
17. No fixed objects, including fire hydrants, trees, and streetlight poles, are allowed within ten feet of a driveway edge, defined as Point A in standard drawing SW-140-1 or equivalent. Fixed objects are defined as anything with breakaway characteristics greater than a four-inch by four-inch wooden post.
18. No new overhead utility lines will be allowed within or across any right of way or sidewalk easement, and existing overhead lines must be relocated underground.

AUTHORITY: Bellevue City Code 14.60; Transportation Department Design Manual; Americans with Disabilities Act
REVIEWER: Randa Kiriakos, Transportation Department

16. Maintenance Agreement – Right of Way Streetscape

Prior to the release of the Landscape Maintenance Assurance Device, the applicant and the City of Bellevue Parks shall enter into an agreement to determine future maintenance responsibilities for the streetscape and streetscape plantings.

AUTHORITY: Land Use Code 20.20.520
REVIEWER: Leah Chulsky, Development Services Department

17. Planting – Right of Way Streetscape

1. Planting shall be done according to the Parks and Community Services Department Environmental Best Management Practices and Design Standards in place at the time of construction.
2. A Parks Department representative shall be on-site to inspect street trees prior to planting and at the time of planting to observe the installation. Contact Parks Department Resource Management at 425-452-6855 at least 24 hours before planting to schedule the inspection.

AUTHORITY: Land Use Code 20.20.520
REVIEWER: Leah Chulsky, Development Services Department

18. Planting – Right of Way Streetscape

Existing City of Bellevue landscaping and irrigation is present in project area. Irrigation systems are not included in 811 locates. Contact City of Bellevue Parks Department before starting work in these areas to coordinate landscape restoration, ensure impacts to off-site landscapes fed by the irrigation system are minimized, determine any tree protection needs, and backfill soil is installed per Parks standards. Protect all existing lateral lines, main lines, sleeving, wiring and components until inspection by Parks irrigation staff before moving forward with planned modifications. Any disruption of existing irrigation function must be short duration as it supplies other streetscape areas along SE 16th. Damage is to be reported immediately to the construction inspector for the project.

AUTHORITY: Land Use Code 20.20.520
REVIEWER: Leah Chulsky, Development Services Department

19. Noise & Construction Hours

The proposal will be subject to normal construction hours of 7 a.m. to 6 p.m., Monday through Friday and 9:00 a.m. to 6:00 p.m. on Saturdays, except for Federal holidays and as further defined by the Bellevue City Code. Proximity to existing residential uses will be given special consideration. Upon written request to PCD, work hours may be extended to 10:00 p.m. if the criteria for extension of work hours as stated in BCC 9.18 can be met and the appropriate mitigation employed.

The use of best available noise abatement technology consistent with feasibility is required during construction to mitigate construction noise impacts to surrounding uses.

AUTHORITY: Bellevue City Code 9.18.020.C & 9.18.040
REVIEWER: Leah Chulsky, Development Services Department

C. PRIOR TO BUILDING PERMIT ISSUANCE:

1. Transportation Impact Fee

Payment of the traffic impact fee will be required at the time of building permit issuance. If multiple building permits will be issued, the impact fee will be tied to the primary above-ground permit. Removal of existing buildings will be eligible for impact fee credit. Impact fees are subject to change and the fee schedule in effect at the time of building permit issuance will apply.

AUTHORITY: Bellevue City Code 22.16
REVIEWER: Randa Kiriakos, Transportation Department

2. Building and Site Plans – Transportation

The building grade and elevations shall be consistent with the curb and sidewalk grade shown in the approved civil engineering plans. During construction, city inspectors may require additional survey work at any time in order to confirm proper elevations. Building plans, landscaping plans, and architectural site plans must accommodate on-site traffic markings and signs and driveway design as specified in the engineering plans. Building plans, landscaping plans, and architectural site plans must comply with vehicle and pedestrian sight distance requirements, as shown on the engineering plans.

AUTHORITY: Bellevue City Code BCC 14.60.060, 110, 120, 150, 180, 181, 190, 240, 241
REVIEWER: Randa Kiriakos, Transportation Department

3. Geotechnical Inspection

The project geotechnical engineer must provide geotechnical inspection during project construction, including retaining walls, subgrades for foundations and footings, and any unusual seepage, slope, or subgrade conditions.

AUTHORITY: Clearing & Grading Code 23.76.050
REVIEWER: Savina Uzunow, Development Services Department, Clearing & Grading Section

4. Provisions for Refuse and Loading

The property owner shall provide an off-street loading space which can access a public street. This must include an off-street location for garbage pick-up, which must be acceptable to the garbage hauler. On-street loading and unloading will not be permitted.

AUTHORITY: Land Use Code 20.20.590.K.4; Bellevue City Code 14.60.180
REVIEWER: Randa Kiriakos, Transportation Department

5. Use of Best Available Noise Abatement Technology

The use of best available noise abatement technology consistent with feasibility is required during construction to mitigate construction noise impacts to surrounding uses.

AUTHORITY: Bellevue City Code 9.18.020.F
REVIEWER: Leah Chulsky, Development Services Department

D. PRIOR TO ISSUANCE OF ANY OCCUPANCY:

1. Landscape Maintenance Assurance Device

File with the Development Services Department a landscape maintenance assurance device prior to TCO approval for a five year period for 20% of the cost of labor and materials for all required landscaping. For the purpose of this permit, maintenance and monitoring shall be completed for a period of five growing seasons. Release of this assurance device is contingent upon receipt of documentation reporting successful establishment in compliance with the mitigation performance standards listed in the project mitigation plan. Land Use inspection of the planting after 5-years is required to release the surety

AUTHORITY: Land Use Code 20.40.490, 20.25H.125.J and 20.25H.220
REVIEWER: Leah Chulsky, Development Services Department

2. Street Frontage Improvements

All street frontage improvements and other required transportation elements, including street light and traffic signal revisions, must be constructed by the applicant and accepted by the Transportation Department inspector. All existing street light and traffic signal apparatus affected by this development, including traffic controllers, pedestrian signal poles, traffic signal poles, and power sources, must be relocated as necessary. Existing overhead lines must be relocated underground. All required improvements must be constructed as per the approved plans or as per direction of the Transportation Department inspector. Bonding or other types of assurance devices will not be accepted in lieu of construction, unless the City requires a delay.

AUTHORITY: Bellevue City Code 14.60; Comprehensive Plan Policy UT-39; Transportation Department Design Manual Sections; and Transportation Department Design Manual Standard Drawings.
REVIEWER: Randa Kiriakos, Transportation Department

3. Pavement Restoration

Pavement restoration associated with street frontage improvements or to repair damaged street surfaces shall be provided as follows:

SE 16th Street is classified as Grind and Overlay required. Should street cuts prove unavoidable or if the street surface is damaged in the construction process, a half-street or full-street (depending on the extent of street cuts or damage) grind and overlay will be required for a minimum of 50 feet.

AUTHORITY: Bellevue City Code 14.60. 250; Design Manual Design Standard #23

REVIEWER: Tim Stever, Transportation Department

4. Geotechnical Recommendations and Inspection:

The project shall be constructed and inspected by the Engineer of Record to verify implementation of the recommended procedures and practices in the geotechnical report found in the reports prepared by prepared by AESI, on April 9, 2018. A report verifying implementation of inspection shall be submitted to Leah Chulsky at lechulsky@bellevuewa.gov prior to receipt of Temporary Certificate of Occupancy.

Development Services Department
City of Bellevue
PO Box 90012
Bellevue, WA 98009-9012

AUTHORITY: Land Use Code 20.30P.140

REVIEWER: Leah Chulsky, Development Services Department

5. Sprinklers

The structure shall be provided with an automatic fire sprinkler system in accordance the International Fire Code as amended by the City of Bellevue. A permit for the fire system shall be obtained from the Fire Department prior to work commencing.

AUTHORITY: International Fire Code 903

REVIEWER: Glen Albright, Fire Department

6. Fire Alarm

A fire alarm system installed in accordance with the International Fire Code and NFPA 72 is required for this structure. Submit revised plans indicating that deferred submittal will be provided.

AUTHORITY: International Fire Code 907

REVIEWER: Glen Albright, Fire Department

7. Smoke Alarm

Smoke alarms are required per the International Fire Code in all sleeping rooms and in the area immediately adjacent to the sleeping rooms.

AUTHORITY: International Fire Code 907
REVIEWER: Glenn Albright, Fire Department

8. Carbon Monoxide Alarm

Carbon monoxide alarms are required in immediately adjacent to all sleeping rooms.

AUTHORITY: International Fire Code 915
REVIEWER: Glen Albright, Fire Department

9. Key Box Access

A key-box access system shall be provided in accordance with the International Fire Code. The location and type shall be approved by the Fire department. Submit revised plans indicating that a Knox box will be provided.

AUTHORITY: International Fire Code 506
REVIEWER: Glen Albright, Fire Department

10. Extinguishing System – Cooking Equipment

Commercial-type cooking equipment shall be protected by an approved automatic extinguishing system. A permit for the installation of the system shall be secured from the Fire Prevention Division prior to work commencing.

AUTHORITY: International Fire Code 904.12
REVIEWER: Glen Albright, Fire Department

11. Senior Housing Agreement

A Senior Housing agreement must be recorded with the King County Recorder's Office, or its successor agency, and filed with the Bellevue City Clerk, restricting senior citizen dwellings, congregate care senior housing, or assisted living to remain for the life of the project.

AUTHORITY: Land Use Code 20.20.440 footnote (4)
REVIEWER: Leah Chulsky, Development Services Department

12. Native Growth Protection Easement

Record with King County a Native Growth Protection Easement that clearly delineates the area to be designated as Native Growth Area. A copy of the recorded Native Growth Protection Area Easement must be submitted to the City of Bellevue prior to the approval of the TCO.

AUTHORITY: Land Use Code 20.25H.030.B
REVIEWER: Leah Chulsky, Development Services Department

13. NGPE Boundary Fence and Signage

Prior to final building inspection, the applicant shall perform a field survey of property boundaries completed by a Washington State Licensed Surveyor. The boundary of the NGPE shall be identified, fenced, and marked with boundary signage that states:

PROTECTED AREA – NO CLEARING

**This fence marks the edge of a Native Growth Protection Area.
Disturbance, vegetation removal, or tree removal beyond this fence is prohibited.**

NGPE boundary fencing and signage shall be of permanent construction and shall be maintained for the duration of the development. Signs must be of size and location to be visible and the boundary fence shall be a minimum of four feet tall.

AUTHORITY: Land Use Code 20.25H.030
REVIEWER: Leah Chulsky, Development Services Department

14. Exterior Building Lighting

All exterior lighting shall include cut-of shields that prevent light impacts to nearby developments. Exterior accent lighting shall be adjustable; applicant will work with planner at TCO to confirm appropriate light levels.

AUTHORITY: Land Use Code 20.25B.050.B
REVIEWER: Leah Chulsky, Development Services Department

15. Rooftop Mechanical Screening

Mechanical equipment which is located on the roof shall be incorporated into the pitched or stepped roof form, and not appear as a separate penthouse or box. Any proposed future changes must be approved by Land Use and uphold the intent and conditions of the original proposal to screen mechanical equipment from above and street level views.

AUTHORITY: Land Use Code 20.25B.040.E
REVIEWER: Leah Chulsky, Development Services Department

16. Noise Levels/Measurements in Sleeping Areas

Noise levels in sleeping areas shall not exceed 40 dBA. The applicant shall measure the noise levels in a random sample of the rooms and submit the findings to the City. If the maximum threshold is exceeded, additional noise mitigation will be required to meet the threshold prior to the issuance of an Occupancy Permit.

AUTHORITY: Bellevue City Code 9.18.045B
REVIEWER: Leah Chulsky, Development Services Department

17. Communication Dishes

Communication dishes greater than one meter (3.28 feet) in diameter shall not be visible from any adjacent residential districts. Communication dishes, antennas and other building appendages require Land Use Approval. Any proposed future changes must be approved by Land Use and uphold the intent and conditions of the original proposal to screen equipment from above and street level views.

AUTHORITY: Land Use Code 20.25B.040.E
REVIEWER: Leah Chulsky, Development Services Department



DEVELOPMENT SERVICES DEPARTMENT
ENVIRONMENTAL COORDINATOR
450 110th Ave NE
BELLEVUE, WA 98009-9012

DETERMINATION OF NON-SIGNIFICANCE

PROPONENT: Silverado Memory Care

LOCATION OF PROPOSAL: 14341 SE 16th St

DESCRIPTION OF PROPOSAL: Design Review and Critical Areas Land Use Permit approval and Conditional Use Permit recommendation for a 21 unit memory care facility located within a newly constructed building. The proposal includes a request to reduce a steep slope critical area buffer.

FILE NUMBERS: 18-126959-LB, 18-126958-LD 18-126964-LO **PLANNER:** Leah Chulsky

The Environmental Coordinator of the City of Bellevue has determined that this proposal does not have a probable significant adverse impact upon the environment. An Environmental Impact Statement (EIS) is not required under RCW 43.21C.030(2)(C). This decision was made after the Bellevue Environmental Coordinator reviewed the completed environmental checklist and information filed with the Land Use Division of the Development Services Department. This information is available to the public on request.

- ☐ There is no comment period for this DNS. There is a 14-day appeal period. Only persons who submitted written comments before the DNS was issued may appeal the decision. A written appeal must be filed in the City Clerk's office by 5:00 p.m. on _____.
- ☒ This DNS is issued after using the optional DNS process in WAC 197-11-355. There is no further comment period on the DNS. There is a 14-day appeal period. Only persons who submitted written comments before the DNS was issued may appeal the decision. A written appeal must be filed in the City Clerk's Office by 5 p.m. on **11/7/2019**
- ☐ This DNS is issued under WAC 197-11-340(2) and is subject to a 14-day comment period from the date below. Comments must be submitted by 5 p.m. on _____. This DNS is also subject to appeal. A written appeal must be filed in the City Clerk's Office by 5:00 p.m. on _____.

This DNS may be withdrawn at any time if the proposal is modified so as to have significant adverse environmental impacts; if there is significant new information indicating a proposals probable significant adverse environmental impacts (unless a non-exempt license has been issued if the proposal is a private project); or if the DNS was procured by misrepresentation or lack of material disclosure.

A handwritten signature in black ink, appearing to be "E. J. ...", written over a horizontal line.

Environmental Coordinator

10/24/2019

Date

OTHERS TO RECEIVE THIS DOCUMENT:

- ☒ State Department of Fish and Wildlife / Stewart.Reinbold@dfw.gov; Christa.Heller@dfw.wa.gov;
- ☒ State Department of Ecology, Shoreline Planner N.W. Region / Jobu461@ecy.wa.gov; sepaunit@ecy.wa.gov
- ☒ Army Corps of Engineers Susan.M.Powell@nws02.usace.army.mil
- ☒ Attorney General ecvolyef@atg.wa.gov
- ☒ Muckleshoot Indian Tribe Karen.Walter@muckleshoot.nsn.us; Fisheries.fileroom@muckleshoot.nsn.us



DEVELOPMENT SERVICES DEPARTMENT
450 110TH AVENUE NE
BELLEVUE, WA 98009-9012

SEPA Environmental Checklist

If you need assistance in completing the checklist or have any questions regarding the environmental review process, please visit the Land Use Desk in the Permit Center between 8 a.m. and 4 p.m., Monday through Friday (Wednesday, 10 to 4) or call or email the Land Use Division at 425-452-4188 or landusereview@bellevuewa.gov. Assistance for the hearing impaired: Dial 711 (Telecommunications Relay Service).

Purpose of checklist:

The City of Bellevue uses this checklist to help determine whether the environmental impacts of your proposal are significant. This information is also helpful to determine if available avoidance, minimization or compensatory mitigation measures will address the probable significant impacts or if an environmental impact statement will be prepared to further analyze the proposal.

Instructions for applicants:

This environmental checklist asks you to describe some basic information about your proposal. Please answer each question accurately and carefully, to the best of your knowledge. You may need to consult with an agency specialist or private consultant for some questions. You may use "not applicable" or "does not apply" only when you can explain why it does not apply and not when the answer is unknown. You may also attach or incorporate by reference additional studies and reports. Please make complete and accurate answers to these questions to the best of your ability in order to avoid delays.

The checklist questions apply to all parts of your proposal, even if you plan to do them over a period of time or on different parcels of land. Attach any additional information that will help describe your proposal or its environmental effects. The City may ask you to explain your answers or provide additional information reasonably related to determining if there may be significant adverse impact.

PLEASE REMEMBER TO SIGN THE CHECKLIST. Electronic signatures are also acceptable.

18-126959-LB, 18-126958-LD
18-126964-LD *2/1/19* 10/24/19

A. Background [\[help\]](#)

1. Name of proposed project, if applicable: [\[help\]](#)
Silverado Bellevue
2. Name of applicant: [\[help\]](#)
Wattenbarger Architects
3. Address and phone number of applicant and contact person: [\[help\]](#)
11000 NE 33rd PL, Bellevue, WA 98004
(425) 453-0606
James Brown
4. Date checklist prepared: [\[help\]](#)
April 16, 2018
5. Agency requesting checklist: [\[help\]](#)
City of Bellevue, Development Services
6. Proposed timing or schedule (including phasing, if applicable): [\[help\]](#)
Construction beginning early 2019 - completion early 2020
7. Do you have any plans for future additions, expansion, or further activity related to or connected with this proposal? If yes, explain. [\[help\]](#)
No
8. List any environmental information you know about that has been prepared, or will be prepared, directly related to this proposal. [\[help\]](#)
Geotechnical Report
Critical Area Reconnaissance Report
9. Do you know whether applications are pending for governmental approvals of other proposals directly affecting the property covered by your proposal? If yes, explain. [\[help\]](#)
No
10. List any government approvals or permits that will be needed for your proposal, if known. [\[help\]](#)
Conditional Use Permit
Building Permit
Clear & Grade, Design Review, Critical Areas Permit
11. Give brief, complete description of your proposal, including the proposed uses and the size of the project and site. There are several questions later in this checklist that ask you to describe certain aspects of your proposal. You do not need to repeat those answers on this page. (Lead agencies may modify this form to include additional specific information on project description.) [\[help\]](#)
Construction of a (2) story assisted living community over 1 level of daylight basement. The building will contain 21 sleeping units as well as supporting service and amenity spaces. The total building footprint is approximately 10,500 SF, and total building area is approximately 29,500 SF.

12. Location of the proposal. Give sufficient information for a person to understand the precise location of your proposed project, including a street address, if any, and section, township, and range, if known. If a proposal would occur over a range of area, provide the range or boundaries of the site(s). Provide a legal description, site plan, vicinity map, and topographic map, if reasonably available. While you should submit any plans required by the agency, you are not required to duplicate maps or detailed plans submitted with any permit applications related to this checklist. [\[help\]](#)

14641 SE 16th St. Bellevue, WA

B. Environmental Elements [\[help\]](#)

1. Earth [\[help\]](#)

- a. General description of the site: [\[help\]](#) (select one): ☐ Flat, ☐ rolling, ☐ hilly, ☒ steep slopes, ☐ mountainous, other: *Click here to enter text.*
- b. What is the steepest slope on the site (approximate percent slope)? [\[help\]](#)
Approximately 65%.
- c. What general types of soils are found on the site (for example, clay, sand, gravel, peat, muck)? If you know the classification of agricultural soils, specify them and note any agricultural land of long-term commercial significance and whether the proposal results in removing any of these soils. [\[help\]](#)
The site is mantled by 3 feet of duff and organic silty sand, which overlies a deposit of medium dense to very dense glacial till consisting of silty sand with gravel. The glacial till is more than 30 feet thick.
- d. Are there surface indications or history of unstable soils in the immediate vicinity? If so, describe. [\[help\]](#)
There are no visible landslide scarps, slide paths, or erosion zones on the site or on the adjacent properties.
- e. Describe the purpose, type, total area, and approximate quantities and total affected area of any filling, excavation, and grading proposed. Indicate source of fill. [\[help\]](#)
Approximately 20,000sf of the site will be graded and excavated to accommodate the building and driveway. Approximate earthwork quantities of 5,300cy cut and 200cy fill (based on basement finish floor of 328.50). Any imported material for the driveway base, structural fill for the building and wall, and topsoil for the landscape and seeded areas will be sourced from an approved local supplier.
- f. Could erosion occur as a result of clearing, construction, or use? If so, generally describe. [\[help\]](#)
Yes, with the extensive grading and utility work required, the

18-126959-LB *2/1/19*
18-126958-LD *10/24/19*
18-126964-LD

standard erosion and sediment control BMPs will be needed to ensure that sediment does not leave the site.

- g. About what percent of the site will be covered with impervious surfaces after project construction (for example, asphalt or buildings)? [\[help\]](#)
Approximately 46.3% of the site will be covered by impervious surfaces after the project is complete.

- h. Proposed measures to reduce or control erosion, or other impacts to the earth, if any: [\[help\]](#)
A Temporary Erosion and Sediment Control Plan (TESCP) and a Storm Water Pollution Prevention Plan (SWPPP) will be prepared for this project. The BMPs included on these plans will be installed and maintained during construction. A CESCL will be provided by the contractor during construction to monitor the storm water runoff.

impacts mitigate by application
of Clear and Trade Code
23.7%

2. Air [\[help\]](#)

- a. What types of emissions to the air would result from the proposal during construction, operation, and maintenance when the project is completed? If any, generally describe and give approximate quantities if known. [\[help\]](#)
Limited emissions related to vehicular and light equipment use during construction. Post construction emissions limited to vehicular use by residents and staff.
- b. Are there any off-site sources of emissions or odor that may affect your proposal? If so, generally describe. [\[help\]](#)
No
- c. Proposed measures to reduce or control emissions or other impacts to air, if any: [\[help\]](#)
None

3. Water [\[help\]](#)

a. Surface Water:

- 1) Is there any surface water body on or in the immediate vicinity of the site (including year-round and seasonal streams, saltwater, lakes, ponds, wetlands)? If yes, describe type and provide names. If appropriate, state what stream or river it flows into. [\[help\]](#)
No
- 2) Will the project require any work over, in, or adjacent to (within 200 feet) the described waters? If yes, please describe and attach available plans. [\[help\]](#)
No
- 3) Estimate the amount of fill and dredge material that would be placed in or removed

18-126959-LB
18-126958-LD 10/24/19
18-126944-LD

from surface water or wetlands and indicate the area of the site that would be affected. Indicate the source of fill material. [\[help\]](#)

None

- 4) Will the proposal require surface water withdrawals or diversions? Give general description, purpose, and approximate quantities if known. [\[help\]](#)

No

- 5) Does the proposal lie within a 100-year floodplain? If so, note location on the site plan. [\[help\]](#)

No

- 6) Does the proposal involve any discharges of waste materials to surface waters? If so, describe the type of waste and anticipated volume of discharge. [\[help\]](#)

No

b. Ground Water:

- 1) Will groundwater be withdrawn from a well for drinking water or other purposes? If so, give a general description of the well, proposed uses and approximate quantities withdrawn from the well. Will water be discharged to groundwater? Give general description, purpose, and approximate quantities if known. [\[help\]](#)

No groundwater will be withdrawn for construction dewatering purposes or for drinking purposes. Due to the impermeable nature of the glacial till overlying the site, no stormwater infiltration systems are planned for the project, nor is any incidental water infiltration expected.

- 2) Describe waste material that will be discharged into the ground from septic tanks or other sources, if any (for example: Domestic sewage; industrial, containing the following chemicals...; agricultural; etc.). Describe the general size of the system, the number of such systems, the number of houses to be served (if applicable), or the number of animals or humans the system(s) are expected to serve. [\[help\]](#)

None

c. Water runoff (including stormwater):

- 1) Describe the source of runoff (including storm water) and method of collection and disposal, if any (include quantities, if known). Where will this water flow? Will this water flow into other waters? If so, describe. [\[help\]](#)

Rainfall from rooftops and pavement will be the primary source for runoff. Stormwater runoff from the roof will be collected by downspout leaders and runoff from the driveway by a trench drain. This water will be detained and released from the site to the City's storm drainage system within SE 16th Street. This water will ultimately reach reach Lake Washington by means of the Mercer Slough.

2) Could waste materials enter ground or surface waters? If so, generally describe. [\[help\]](#)
No

3) Does the proposal alter or otherwise affect drainage patterns in the vicinity of the site? If so, describe. [\[help\]](#)

No. Storm water from the site will be collected, detained, and released from the site at the pre-developed rate.

d. Proposed measures to reduce or control surface, ground, and runoff water, and drainage pattern impacts, if any: [\[help\]](#)

A stormwater facility controlling peak runoff flows during storm events is part of the proposal to reduce drainage impacts.

impacts mitigated by
application of Clear & trade
code 23.76

4. Plants [\[help\]](#)

a. Check the types of vegetation found on the site: [\[help\]](#)

☒deciduous tree: alder, maple, aspen, other: Click here to enter text.

☒evergreen tree: fir, cedar, pine, other: Click here to enter text.

☒shrubs

☐grass

☐pasture

☐crop or grain

☐Orchards, vineyards or other permanent crops.

☐wet soil plants: cattail, buttercup, bullrush, skunk cabbage, other: Click here to enter text.

☐water plants: water lily, eelgrass, milfoil, other: Click here to enter text.

☐Other types of vegetation: Click here to enter text.

b. What kind and amount of vegetation will be removed or altered? [\[help\]](#)

Removal and mitigation of limited trees in accordance with local codes. Removal of invasive species and restoration to native plants.

c. List threatened and endangered species known to be on or near the site. [\[help\]](#)

None known.

d. Proposed landscaping, use of native plants, or other measures to preserve or enhance vegetation on the site, if any: [\[help\]](#)

Use of native plants

e. List all noxious weeds and invasive species known to be on or near the site. [\[help\]](#)

English Ivy

5. Animals [\[help\]](#)

a. List any birds and other animals which have been observed on or near the site or are known

to be on or near the site. [\[help\]](#)

Examples include:

birds: ☐hawk, ☐heron, ☐eagle, ☐songbirds, other: American crow, American robin, black-capped chickadee, dark-eyed junco, European starling, rufous-sided towhee, song sparrow, steller's jay and winter wren.

mammals: ☐deer, ☐bear, ☐elk, ☐beaver, other: *none observed*

fish: ☐bass, ☐salmon, ☐trout, ☐herring, ☐shellfish, other: *none*

- b. List any threatened and endangered species known to be on or near the site. [\[help\]](#)

None identified

- c. Is the site part of a migration route? If so, explain. [\[help\]](#)

All of Washington is within the Pacific Flyway

- d. Proposed measures to preserve or enhance wildlife, if any: [\[help\]](#)

None

- e. List any invasive animal species known to be on or near the site. [\[help\]](#)

None known

6. Energy and Natural Resources [\[help\]](#)

- a. What kinds of energy (electric, natural gas, oil, wood stove, solar) will be used to meet the completed project's energy needs? Describe whether it will be used for heating, manufacturing, etc. [\[help\]](#)

Electric, Gas - power and heating

- b. Would your project affect the potential use of solar energy by adjacent properties? If so, generally describe. [\[help\]](#)

No

- c. What kinds of energy conservation features are included in the plans of this proposal?

List other proposed measures to reduce or control energy impacts, if any: [\[help\]](#)

Low-e appliances, LED lighting

7. Environmental Health [\[help\]](#)

- a. Are there any environmental health hazards, including exposure to toxic chemicals, risk of fire and explosion, spill, or hazardous waste, that could occur as a result of this proposal? If so, describe. [\[help\]](#)

No

- 1) Describe any known or possible contamination at the site from present or past uses.

[\[help\]](#)

None known

- 2) Describe existing hazardous chemicals/conditions that might affect project development

and design. This includes underground hazardous liquid and gas transmission pipelines located within the project area and in the vicinity. [\[help\]](#)

None known

- 3) Describe any toxic or hazardous chemicals that might be stored, used, or produced during the project's development or construction, or at any time during the operating life of the project. [\[help\]](#)

None

- 4) Describe special emergency services that might be required. [\[help\]](#)

None

- 5) Proposed measures to reduce or control environmental health hazards, if any: [\[help\]](#)

None

b. Noise [\[help\]](#)

- 1) What types of noise exist in the area which may affect your project (for example: traffic, equipment, operation, other)? [\[help\]](#)

Low levelis of vehicular traffic

- 2) What types and levels of noise would be created by or associated with the project on a short-term or a long-term basis (for example: traffic, construction, operation, other)?

Indi-cate what hours noise would come from the site. [\[help\]](#)

Short term construction noise

- 3) Proposed measures to reduce or control noise impacts, if any: [\[help\]](#)

Contruction to occur only within ours permitted by the City of Bellevue

impacts mitigated by application of BCC 9.18

8. Land and Shoreline Use [\[help\]](#)

- a. What is the current use of the site and adjacent properties? Will the proposal affect current land uses on nearby or adjacent properties? If so, describe. [\[help\]](#)

Commercial, Single Family, Multi-family. Proposal will have no impacts to adjacent land uses.

- b. Has the project site been used as working farmlands or working forest lands? If so, describe. How much agricultural or forest land of long-term commercial significance will be converted to other uses as a result of the proposal, if any? If resource lands have not been designated, how many acres in farmland or forest land tax status will be converted to nonfarm or nonforest use? [\[help\]](#)

No

- 1) Will the proposal affect or be affected by surrounding working farm or forest land normal business operations, such as oversize equipment access, the application of pesticides, tilling, and harvesting? If so, how: [\[help\]](#)

No

- c. Describe any structures on the site. [\[help\]](#)

None

- d. Will any structures be demolished? If so, what? [\[help\]](#)
N/A
- e. What is the current zoning classification of the site? [\[help\]](#)
Neighborhood Business, Transition District overlay
- f. What is the current comprehensive plan designation of the site? [\[help\]](#)
Commercial / Retail
- g. If applicable, what is the current shoreline master program designation of the site? [\[help\]](#)
N/A
- h. Has any part of the site been classified as a critical area by the city or county? If so, specify. [\[help\]](#)
Yes, a small portion of approximately 1,400 SF is considered to be a steep slope by the City of Bellevue
- i. Approximately how many people would reside or work in the completed project? [\[help\]](#)
42 residents, approximately 10 staff at any given time.
- j. Approximately how many people would the completed project displace? [\[help\]](#)
None
- k. Proposed measures to avoid or reduce displacement impacts, if any: [\[help\]](#)
N/A
- l. Proposed measures to ensure the proposal is compatible with existing and projected land uses and plans, if any: [\[help\]](#)
The project will undergo a Conditional Use and Design Review process with the City of Bellevue
- m. Proposed measures to ensure the proposal is compatible with nearby agricultural and forest lands of long-term commercial significance, if any: [\[help\]](#)
N/A

9. Housing [\[help\]](#)

- a. Approximately how many units would be provided, if any? Indicate whether high, middle, or low-income housing. [\[help\]](#)
21 sleeping units for memory care residents. Middle to high income.
- b. Approximately how many units, if any, would be eliminated? Indicate whether high, middle, or low-income housing. [\[help\]](#)
None
- c. Proposed measures to reduce or control housing impacts, if any: [\[help\]](#)
None

10. Aesthetics [\[help\]](#)

- a. What is the tallest height of any proposed structure(s), not including antennas; what is the principal exterior building material(s) proposed? [\[help\]](#)
Approximately 30'
- b. What views in the immediate vicinity would be altered or obstructed? [\[help\]](#)
No significant views would be obstructed by the project.
- c. Proposed measures to reduce or control aesthetic impacts, if any: [\[help\]](#)
Restoration of invasive species, Replacement trees for tree removal, along with transition district buffer will help maintain a visual buffer between adjacent lower impact uses. Design review will assure that the project is consistent with the adjacent neighborhood and the city's design standards.

11. Light and Glare [\[help\]](#)

- a. What type of light or glare will the proposal produce? What time of day would it mainly occur? [\[help\]](#)
Limited entry and path lighting will be present during nighttime hours.
- b. Could light or glare from the finished project be a safety hazard or interfere with views? [\[help\]](#)
No
- c. What existing off-site sources of light or glare may affect your proposal? [\[help\]](#)
None
- d. Proposed measures to reduce or control light and glare impacts, if any: [\[help\]](#)
Indirect fixtures for exterior lighting.

12. Recreation [\[help\]](#)

- a. What designated and informal recreational opportunities are in the immediate vicinity? [\[help\]](#)
Some retail and parks within walking distance.
- b. Would the proposed project displace any existing recreational uses? If so, describe. [\[help\]](#)
No
- c. Proposed measures to reduce or control impacts on recreation, including recreation opportunities to be provided by the project or applicant, if any: [\[help\]](#)
Project will contain both interior and exterior recreation space for the residents.

13. Historic and cultural preservation [\[help\]](#)

- a. Are there any buildings, structures, or sites, located on or near the site that are over 45

years old listed in or eligible for listing in national, state, or local preservation registers located on or near the site? If so, specifically describe. [\[help\]](#)

No

- b. Are there any landmarks, features, or other evidence of Indian or historic use or occupation? This may include human burials or old cemeteries. Are there any material evidence, artifacts, or areas of cultural importance on or near the site? Please list any professional studies conducted at the site to identify such resources. [\[help\]](#)

None known

- c. Describe the methods used to assess the potential impacts to cultural and historic resources on or near the project site. Examples include consultation with tribes and the department of archeology and historic preservation, archaeological surveys, historic maps, GIS data, etc.

[\[help\]](#)

None

- d. Proposed measures to avoid, minimize, or compensate for loss, changes to, and disturbance to resources. Please include plans for the above and any permits that may be required. [\[help\]](#)

None

14. Transportation [\[help\]](#)

- a. Identify public streets and highways serving the site or affected geographic area and describe proposed access to the existing street system. Show on site plans, if any. [\[help\]](#)

SE 16th St.

- b. Is the site or affected geographic area currently served by public transit? If so, generally describe. If not, what is the approximate distance to the nearest transit stop? [\[help\]](#)

Yes, Bus route. Nearest service is approximately 1/4 mile away on 145th St.

- c. How many additional parking spaces would the completed project or non-project proposal have? How many would the project or proposal eliminate? [\[help\]](#)

13 new parking stalls, 1 new loading stall

- d. Will the proposal require any new or improvements to existing roads, streets, pedestrian, bicycle or state transportation facilities, not including driveways? If so, generally describe (indicate whether public or private). [\[help\]](#)

Limited sidewalk and ROW improvements to bring the frontage up to current city standards.

- e. Will the project or proposal use (or occur in the immediate vicinity of) water, rail, or air transportation? If so, generally describe. [\[help\]](#)

No

- f. How many vehicular trips per day would be generated by the completed project or proposal? If known, indicate when peak volumes would occur and what percentage of the volume would be trucks (such as commercial and nonpassenger vehicles). What data or transportation models were used to make these estimates? [\[help\]](#)

An increase of approximately 8 new a.m. peak hour trips and 9

18-126959-LB 10/24/19
18-126958-LD
18-126964-LD

juj

new p.m. peak hour vehicular trips are estimated with the project, and are not expected to generate any significant adverse traffic operational impacts or trigger concurrency review

- g. Will the proposal interfere with, affect or be affected by the movement of agricultural and forest products on roads or streets in the area? If so, generally describe. [\[help\]](#)
No

- h. Proposed measures to reduce or control transportation impacts, if any: [\[help\]](#)
None

15. Public Services [\[help\]](#)

- a. Would the project result in an increased need for public services (for example: fire protection, police protection, public transit, health care, schools, other)? If so, generally describe. [\[help\]](#)
Project will result in a limited increase to fire, police, transit, health care, to serve the anticipated 42 residents.
- b. Proposed measures to reduce or control direct impacts on public services, if any. [\[help\]](#)
Completed project will encourage staff to use public transit.

16. Utilities [\[help\]](#)

- a. Circle utilities currently available at the site: [\[help\]](#)
electricity, natural gas, water, refuse service, telephone, sanitary sewer, septic system, other
Electric, Gas, Water, Telephone, Refuse, Sewer
- c. Describe the utilities that are proposed for the project, the utility providing the service, and the general construction activities on the site or in the immediate vicinity which might be needed. [\[help\]](#)
*New power and gas service will be provided by PSE.
Telecommunication service will be provided by Centurylink or Comcast. New domestic, irrigation, and fire service will be provided by the City of Bellevue. New sanitary sewer service will be provided by the City of Bellevue.*

C. Signature [\[help\]](#)

The above answers are true and complete to the best of my knowledge. I understand that the lead agency is relying on them to make its decision.

Signature: _____

Name of signee: *James Brown*

Position and Agency/Organization: *Wattenbarger Architects*

Date Submitted: *September 14, 2018*

18-126957-LB 10/24/19
18-126958-LD
18-126964-LD

Blank

MASSING MODEL



ZONING AND LAND USE DATA

SITE ADDRESS 14341 SE 16TH ST, BELLEVUE, WA
PARCEL P. 800390-0271
ZONED NB - NEIGHBORHOOD BUSINESS
OVERLAY - TRANSITION AREA DESIGN DISTRICT, CRITICAL AREA OVERLAY DISTRICT
SITE AREA = 35,100 SF
APPROXIMATELY 10% SUBMITTED AS A CONDITIONAL USE

[illegible][illegible]

Over 25,000 titles

the business (24.04) compared to the 19.81 in 2003, a 26.3 per cent increase. The average return on assets for the 100 largest banks in the United States was 1.05 per cent in 2004, compared to 0.95 per cent in 2003, a 10.5 per cent increase. The average return on equity for the 100 largest banks in the United States was 15.1 per cent in 2004, compared to 14.1 per cent in 2003, a 7.1 per cent increase. The average return on capital for the 100 largest banks in the United States was 18.1 per cent in 2004, compared to 17.1 per cent in 2003, a 5.8 per cent increase. The average return on assets for the 100 largest banks in the United States was 1.05 per cent in 2004, compared to 0.95 per cent in 2003, a 10.5 per cent increase. The average return on equity for the 100 largest banks in the United States was 15.1 per cent in 2004, compared to 14.1 per cent in 2003, a 7.1 per cent increase. The average return on capital for the 100 largest banks in the United States was 18.1 per cent in 2004, compared to 17.1 per cent in 2003, a 5.8 per cent increase.

LOT COVERAGE PROPOSED = +/- 10.4245F

BASE DENSITY ALLOWED = 15 x 605 ACRES = 12 Densities Units

DENSITY ADJUSTED FOR CH

DENSITY CALCULATION

APPROXIMATE AREA = 10000

CRITICAL MEDIA •
BUFFERS •
7500 •

$\|U\| = 2.36\%$
 SUBSET = 2.36%
 ...
 ...
 ...

$$(15 \text{ dollars} \times 26.018 \text{ g/g}) + (15 \text{ dollars} \times 9.042 \text{ g/g}) + (15 \text{ dollars} \times 12.018 \text{ g/g}) = 0.38 + (15) \times (9.042)(43.560)(65) = 2.03$$

Density allowed = 10 39 chewing units

10.99 X 2 = 21.98 UNITS = (42 BEDS)

^apre footcandle (22) Opposite far actual season driving, Congregatio care sensor housing and assisted
 lesson "a cabriolante" a. 600m² units less than 600 square feet count as one-half unit and units 600 square
 feet or more count as one unit.

1990年6月10日

PROPOSED = 21 SLEEPING UNITS (42 beds)

BUILDING DATA

TYPE OF CONSTRUCTION 2 FLOORS OF V.A OVER BASEMENT OF 1A
OCCUPANCY 11 CONDITION #2, A, S, 2, B
INFLUENCE 11 SPRINKLERS THROUGHOUT

GROSS BUILDING AREAS	
LEVEL	AREA S.F.

PARKING SCHEDULE	
DATE/TIME	COUNT
ACCESSIBLE VEH	1
COMPACT	8
CHARGED	3
TOTAL	12

UNIT SCHEDULE		
UNIT NO.	AREA	MAINT.
101	101 ST	101 ST
102	101 ST	101 ST
103	101 ST	101 ST
104	101 ST	101 ST
105	101 ST	101 ST
106	101 ST	101 ST
107	101 ST	101 ST
108	101 ST	101 ST
109	101 ST	101 ST
110	101 ST	101 ST
111	101 ST	101 ST
112	101 ST	101 ST
113	101 ST	101 ST
114	101 ST	101 ST
115	101 ST	101 ST
116	101 ST	101 ST
117	101 ST	101 ST
118	101 ST	101 ST
119	101 ST	101 ST
120	101 ST	101 ST
121	101 ST	101 ST
122	101 ST	101 ST
123	101 ST	101 ST
124	101 ST	101 ST
125	101 ST	101 ST
126	101 ST	101 ST
127	101 ST	101 ST
128	101 ST	101 ST
129	101 ST	101 ST
130	101 ST	101 ST
131	101 ST	101 ST
132	101 ST	101 ST
133	101 ST	101 ST
134	101 ST	101 ST
135	101 ST	101 ST
136	101 ST	101 ST
137	101 ST	101 ST
138	101 ST	101 ST
139	101 ST	101 ST
140	101 ST	101 ST
141	101 ST	101 ST
142	101 ST	101 ST
143	101 ST	101 ST
144	101 ST	101 ST
145	101 ST	101 ST
146	101 ST	101 ST
147	101 ST	101 ST
148	101 ST	101 ST
149	101 ST	101 ST
150	101 ST	101 ST
151	101 ST	101 ST
152	101 ST	101 ST
153	101 ST	101 ST
154	101 ST	101 ST
155	101 ST	101 ST
156	101 ST	101 ST
157	101 ST	101 ST
158	101 ST	101 ST
159	101 ST	101 ST
160	101 ST	101 ST
161	101 ST	101 ST
162	101 ST	101 ST
163	101 ST	101 ST
164	101 ST	101 ST
165	101 ST	101 ST
166	101 ST	101 ST
167	101 ST	101 ST
168	101 ST	101 ST
169	101 ST	101 ST
170	101 ST	101 ST
171	101 ST	101 ST
172	101 ST	101 ST
173	101 ST	101 ST
174	101 ST	101 ST
175	101 ST	101 ST
176	101 ST	101 ST
177	101 ST	101 ST
178	101 ST	101 ST
179	101 ST	101 ST
180	101 ST	101 ST
181	101 ST	101 ST
182	101 ST	101 ST
183	101 ST	101 ST
184	101 ST	101 ST
185	101 ST	101 ST
186	101 ST	101 ST
187	101 ST	101 ST
188	101 ST	101 ST
189	101 ST	101 ST
190	101 ST	101 ST
191	101 ST	101 ST
192	101 ST	101 ST
193	101 ST	101 ST
194	101 ST	101 ST
195	101 ST	101 ST
196	101 ST	101 ST
197	101 ST	101 ST
198	101 ST	101 ST
199	101 ST	101 ST
200	101 ST	101 ST
201	101 ST	101 ST
202	101 ST	101 ST
203	101 ST	101 ST
204	101 ST	101 ST
205	101 ST	101 ST
206	101 ST	101 ST
207	101 ST	101 ST
208	101 ST	101 ST
209	101 ST	101 ST
210	101 ST	101 ST
211	101 ST	101 ST
212	101 ST	101 ST

2ND FL DOWN		1ST FL DOWN	
107	343 SF	107	343 SF
108	343 SF	108	343 SF
109	343 SF	109	343 SF
110	343 SF	110	343 SF
111	343 SF	111	343 SF
112	343 SF	112	343 SF
113	343 SF	113	343 SF
114	343 SF	114	343 SF
115	343 SF	115	343 SF
116	343 SF	116	343 SF
117	343 SF	117	343 SF
118	343 SF	118	343 SF
119	343 SF	119	343 SF
120	343 SF	120	343 SF
121	343 SF	121	343 SF
122	343 SF	122	343 SF
123	343 SF	123	343 SF
124	343 SF	124	343 SF
125	343 SF	125	343 SF
2ND FL DOWN TOTAL: 21		1ST FL DOWN TOTAL: 21	

DRAWING INDEX

[illegible]

PROJECT DIRECTORY

SWINERD
6400 OAK CANYON, Ste. 200
FARMINGTON, NM 87401
(505) 424-1716
jtrayner@swinerd.com

CH2M
11525 KIRKLAND WAY, Ste. 310
KIRKLAND, WA 98033
(206) 245-7200
Phil@ch2m.com

GEOTECH
ASSOCIATED EARTH
TECHNOLOGIES, INC.
1332 COMMERCIAL ST., 102
TACOMA, WA 98402
(253) 722-2882
jim.ward@geotech.com

ENVIRONMENTAL CONSULTANT
WETLAND RESOURCES
INTERNATIONAL, INC.
105
EVERETT, WA 98201
(425) 377-3174
craig@wetlandresources.com


ARCHITECT
WATTENBARGER ARCHITECTS
11000 NE 33rd PLACE, SUITE 102
BELLEVUE, WA 98004
(206) 453-6804
james@wattebnarger.com




LANDSCAPE ARCHITECT
RICHARD WARD ASSOCIATES
11000 NE 33rd PLACE, SUITE 102
BELLEVUE, WA 98004
(206) 453-6804
rward21@earthlink.net

TRANSPORTATION CONSULTANT
PROFESSIONAL ENGINEERING
(TENN)
PO BOX 52524
SEATTLE, WA 98155
(206) 461-1100
info@ward@cnw.com

INTERIOR
CREATIVE LANDSCAPE
SOLUTIONS
(425) 890-3868
springwater@gsni.com

VICINITY MAP






Sheet	Notes	Scale	Section
1	BASEMENT PLAN DATE: 11/10/10	1/16" = 1'-0"	3
2	FIRST FLOOR PLAN DATE: 11/10/10	1/16" = 1'-0"	3
3	SECOND FLOOR PLAN DATE: 11/10/10	1/16" = 1'-0"	3

Occupancy Load Tabulation Per 2015 IBC Table...						
FORM NO.	NAME	OCCUPANCY CLASSIFICATION	OCCUPANCY USE	AREA	S.F. PER OCC.	OCCUPANTS
001	POST	10	Post Office	85.9	100	100
002	POST OFFICE	10	Post Office	100	100	100
003	POST OFFICE	10	Post Office	211.5	100	100
004	U.S. OFFICE	10	U.S. Office	210	100	100
005	U.S. OFFICE	10	U.S. Office	210	100	100
006	U.S. OFFICE	10	U.S. Office	210	100	100
007	U.S. OFFICE	10	U.S. Office	210	100	100
008	U.S. OFFICE	10	U.S. Office	210	100	100
009	U.S. OFFICE	10	U.S. Office	210	100	100
010	U.S. OFFICE	10	U.S. Office	210	100	100
011	U.S. OFFICE	10	U.S. Office	210	100	100
012	U.S. OFFICE	10	U.S. Office	210	100	100
013	U.S. OFFICE	10	U.S. Office	210	100	100
014	U.S. OFFICE	10	U.S. Office	210	100	100
015	U.S. OFFICE	10	U.S. Office	210	100	100
016	U.S. OFFICE	10	U.S. Office	210	100	100
017	U.S. OFFICE	10	U.S. Office	210	100	100
018	U.S. OFFICE	10	U.S. Office	210	100	100
019	U.S. OFFICE	10	U.S. Office	210	100	100
020	U.S. OFFICE	10	U.S. Office	210	100	100
021	U.S. OFFICE	10	U.S. Office	210	100	100
022	U.S. OFFICE	10	U.S. Office	210	100	100
023	U.S. OFFICE	10	U.S. Office	210	100	100
024	U.S. OFFICE	10	U.S. Office	210	100	100
025	U.S. OFFICE	10	U.S. Office	210	100	100
026	U.S. OFFICE	10	U.S. Office	210	100	100
027	U.S. OFFICE	10	U.S. Office	210	100	100
028	U.S. OFFICE	10	U.S. Office	210	100	100
029	U.S. OFFICE	10	U.S. Office	210	100	100
030	U.S. OFFICE	10	U.S. Office	210	100	100
031	U.S. OFFICE	10	U.S. Office	210	100	100
032	U.S. OFFICE	10	U.S. Office	210	100	100
033	U.S. OFFICE	10	U.S. Office	210	100	100
034	U.S. OFFICE	10	U.S. Office	210	100	100
035	U.S. OFFICE	10	U.S. Office	210	100	100
036	U.S. OFFICE	10	U.S. Office	210	100	100
037	U.S. OFFICE	10	U.S. Office	210	100	100
038	U.S. OFFICE	10	U.S. Office	210	100	100
039	U.S. OFFICE	10	U.S. Office	210	100	100
040	U.S. OFFICE	10	U.S. Office	210	100	100
041	U.S. OFFICE	10	U.S. Office	210	100	100
042	U.S. OFFICE	10	U.S. Office	210	100	100
043	U.S. OFFICE	10	U.S. Office	210	100	100
044	U.S. OFFICE	10	U.S. Office	210	100	100
045	U.S. OFFICE	10	U.S. Office	210	100	100
046	U.S. OFFICE	10	U.S. Office	210	100	100
047	U.S. OFFICE	10	U.S. Office	210	100	100
048	U.S. OFFICE	10	U.S. Office	210	100	100
049	U.S. OFFICE	10	U.S. Office	210	100	100
050	U.S. OFFICE	10	U.S. Office	210	100	100
051	U.S. OFFICE	10	U.S. Office	210	100	100
052	U.S. OFFICE	10	U.S. Office	210	100	100
053	U.S. OFFICE	10	U.S. Office	210	100	100
054	U.S. OFFICE	10	U.S. Office	210	100	100
055	U.S. OFFICE	10	U.S. Office	210	100	100
056	U.S. OFFICE	10	U.S. Office	210	100	100
057	U.S. OFFICE	10	U.S. Office	210	100	100
058	U.S. OFFICE	10	U.S. Office	210	100	100
059	U.S. OFFICE	10	U.S. Office	210	100	100
060	U.S. OFFICE	10	U.S. Office	210	100	100
061	U.S. OFFICE	10	U.S. Office	210	100	100
062	U.S. OFFICE	10	U.S. Office	210	100	100
063	U.S. OFFICE	10	U.S. Office	210	100	100
064	U.S. OFFICE	10	U.S. Office	210	100	100
065	U.S. OFFICE	10	U.S. Office	210	100	100
066	U.S. OFFICE	10	U.S. Office	210	100	100
067	U.S. OFFICE	10	U.S. Office	210	100	100
068	U.S. OFFICE	10	U.S. Office	210	100	100
069	U.S. OFFICE	10	U.S. Office	210	100	100
070	U.S. OFFICE	10	U.S. Office	210	100	100
071	U.S. OFFICE	10	U.S. Office	210	100	100
072	U.S. OFFICE	10	U.S. Office	210	100	100
073	U.S. OFFICE	10	U.S. Office	210	100	100
074	U.S. OFFICE	10	U.S. Office	210	100	100
075	U.S. OFFICE	10	U.S. Office	210	100	100
076	U.S. OFFICE	10	U.S. Office	210	100	100
077	U.S. OFFICE	10	U.S. Office	210	100	100
078	U.S. OFFICE	10	U.S. Office	210	100	100
079	U.S. OFFICE	10	U.S. Office	210	100	100
080	U.S. OFFICE	10	U.S. Office	210	100	100
081	U.S. OFFICE	10	U.S. Office	210	100	100
082	U.S. OFFICE	10	U.S. Office	210	100	100
083	U.S. OFFICE	10	U.S. Office	210	100	100
084	U.S. OFFICE	10	U.S. Office	210	100	100
085	U.S. OFFICE	10	U.S. Office	210	100	100
086	U.S. OFFICE	10	U.S. Office	210	100	100
087	U.S. OFFICE	10	U.S. Office	210	100	100
088	U.S. OFFICE	10	U.S. Office	210	100	100
089	U.S. OFFICE	10	U.S. Office	210	100	100
090	U.S. OFFICE	10	U.S. Office	210	100	100
091	U.S. OFFICE	10	U.S. Office	210	100	100
092	U.S. OFFICE	10	U.S. Office	210	100	100
093	U.S. OFFICE	10	U.S. Office	210	100	100
094	U.S. OFFICE	10	U.S. Office	210	100	100
095	U.S. OFFICE	10	U.S. Office	210	100	100
096	U.S. OFFICE	10	U.S. Office	210	100	100
097	U.S. OFFICE	10	U.S. Office	210	100	100
098	U.S. OFFICE	10	U.S. Office	210	100	100
099	U.S. OFFICE	10	U.S. Office	210	100	100
100	U.S. OFFICE	10	U.S. Office	210	100	100

[illegible]

RM. NO.	NAME	OCCUPANCY CLASSIFICATION	OCCUPANTS
107	UNIT B3	1	1
108	UNIT B3	1	1
109	UNIT B3	1	1
110	UNIT B3	1	1
111	UNIT B3	1	1
112	UNIT B3	1	1
113	UNIT B3	1	1
114	UNIT B3	1	1
115	UNIT B3	1	1
116	UNIT B3	1	1
117	UNIT B3	1	1
118	UNIT B3	1	1
119	UNIT B3	1	1
120	UNIT B3	1	1
121	UNIT B3	1	1
122	UNIT B3	1	1
123	UNIT B3	1	1
124	UNIT B3	1	1
125	UNIT B3	1	1
126	UNIT B3	1	1
127	UNIT B3	1	1
128	UNIT B3	1	1
129	UNIT B3	1	1
130	UNIT B3	1	1
131	UNIT B3	1	1
132	UNIT B3	1	1
133	UNIT B3	1	1
134	UNIT B3	1	1
135	UNIT B3	1	1
136	UNIT B3	1	1
137	UNIT B3	1	1
138	UNIT B3	1	1
139	UNIT B3	1	1
140	UNIT B3	1	1
141	UNIT B3	1	1
142	UNIT B3	1	1
143	UNIT B3	1	1
144	UNIT B3	1	1
145	UNIT B3	1	1
146	UNIT B3	1	1
147	UNIT B3	1	1
148	UNIT B3	1	1
149	UNIT B3	1	1
150	UNIT B3	1	1
151	UNIT B3	1	1
152	UNIT B3	1	1
153	UNIT B3	1	1
154	UNIT B3	1	1
155	UNIT B3	1	1
156	UNIT B3	1	1
157	UNIT B3	1	1
158	UNIT B3	1	1
159	UNIT B3	1	1
160	UNIT B3	1	1
161	UNIT B3	1	1
162	UNIT B3	1	1
163	UNIT B3	1	1
164	UNIT B3	1	1
165	UNIT B3	1	1
166	UNIT B3	1	1
167	UNIT B3	1	1
168	UNIT B3	1	1
169	UNIT B3	1	1
170	UNIT B3	1	1
171	UNIT B3	1	1
172	UNIT B3	1	1
173	UNIT B3	1	1
174	UNIT B3	1	1
175	UNIT B3	1	1
176	UNIT B3	1	1
177	UNIT B3	1	1
178	UNIT B3	1	1
179	UNIT B3	1	1
180	UNIT B3	1	1
181	UNIT B3	1	1
182	UNIT B3	1	1
183	UNIT B3	1	1
184	UNIT B3	1	1
185	UNIT B3	1	1
186	UNIT B3	1	1
187	UNIT B3	1	1
188	UNIT B3	1	1
189	UNIT B3	1	1
190	UNIT B3	1	1
191	UNIT B3	1	1
192	UNIT B3	1	1
193	UNIT B3	1	1
194	UNIT B3	1	1
195	UNIT B3	1	1
196	UNIT B3	1	1
197	UNIT B3	1	1
198	UNIT B3	1	1
199	UNIT B3	1	1
200	UNIT B3	1	1
201	UNIT B3	1	1
202	UNIT B3	1	1
203	UNIT B3	1	1
204	UNIT B3	1	1
205	UNIT B3	1	1
206	UNIT B3	1	1
207	UNIT B3	1	1
208	UNIT B3	1	1
209	UNIT B3	1	1
210	UNIT B3	1	1
211	UNIT B3	1	1
212	UNIT B3	1	1
213	UNIT B3	1	1
214	UNIT B3	1	1
215	UNIT B3	1	1
216	UNIT B3	1	1
217	UNIT B3	1	1
218	UNIT B3	1	1
219	UNIT B3	1	1
220	UNIT B3	1	1
221	UNIT B3	1	1
222	UNIT B3	1	1
223	UNIT B3	1	1
224	UNIT B3	1	1
225	UNIT B3	1	1</

☐ A-2
☐ A-3
☐ B
☐ S-1
☐ S-2



NOTES


OCCUPANCY TABULATION - BASEMENT

NAME	AREA	CLASSIFICATION	USE	SERIAL OCCUPANT	TOTAL OCCUPANTS
MARTIN LUTHER KING JR.	A-102 SP	C-2	Planning Group I	279	34
JAMES EARL RAY	B-67 SP	A-2	RESEARCH, Commercial	10	5
JOHN EDGAR HOOVER	D-208 SP	B	Business Awa II	210	11
WILLIAM F. BUCKLEY	E-127 SP	A-3	Assembly, Unrepresented (public and private)	15	33
ALBERT EINSTEIN	F-127 SP	B-1	Access Area, Storage Areas, Application of Equipment Repair	50	2

OCCUPANCY CLASSIFICATION

- ☐ A-2
- ☐ A-3
- ☐ B
- ☐ I-1
- ☐ S-1

NOTES:
ACCESSIBLE MEANS OF EGRESS THROUGH EXTERIOR DOOR AND ELEVATOR 1



OCCUPANCY TABULATION - 1ST FL


NAME	AREA	CLASSIFICATION	SF / OCCUPANT	TOTAL
RECEPTION	1,000 SF	A-2	100	100
LOBBY	1,000 SF	A-2	100	100
WAITING AREA	1,000 SF	A-2	100	100
OFFICES	1,000 SF	A-2	100	100
RESTROOMS	1,000 SF	A-2	100	100
ELEVATOR	1,000 SF	A-2	100	100
STAIRS	1,000 SF	A-2	100	100
CORRIDOR	1,000 SF	A-2	100	100
UNIT B1	1,000 SF	A-2	100	100
UNIT B2	1,000 SF	A-2	100	100
UNIT B3	1,000 SF	A-2	100	100
UNIT B4	1,000 SF	A-2	100	100
UNIT B5	1,000 SF	A-2	100	100
UNIT B6	1,000 SF	A-2	100	100
UNIT B7	1,000 SF	A-2	100	100
UNIT B8	1,000 SF	A-2	100	100
UNIT B9	1,000 SF	A-2	100	100
UNIT B10	1,000 SF	A-2	100	100
UNIT B11	1,000 SF	A-2	100	100
UNIT B12	1,000 SF	A-2	100	100
UNIT B13	1,000 SF	A-2	100	100
UNIT B14	1,000 SF	A-2	100	100
UNIT B15	1,000 SF	A-2	100	100
UNIT B16	1,000 SF	A-2	100	100
UNIT B17	1,000 SF	A-2	100	100
UNIT B18	1,000 SF	A-2	100	100
UNIT B19	1,000 SF	A-2	100	100
UNIT B20	1,000 SF	A-2	100	100
UNIT B21	1,000 SF	A-2	100	100
UNIT B22	1,000 SF	A-2	100	100
UNIT B23	1,000 SF	A-2	100	100
UNIT B24	1,000 SF	A-2	100	100
UNIT B25	1,000 SF	A-2	100	100
UNIT B26	1,000 SF	A-2	100	100
UNIT B27	1,000 SF	A-2	100	100
UNIT B28	1,000 SF	A-2	100	100
UNIT B29	1,000 SF	A-2	100	100
UNIT B30	1,000 SF	A-2	100	100
UNIT B31	1,000 SF	A-2	100	100
UNIT B32	1,000 SF	A-2	100	100
UNIT B33	1,000 SF	A-2	100	100
UNIT B34	1,000 SF	A-2	100	100
UNIT B35	1,000 SF	A-2	100	100
UNIT B36	1,000 SF	A-2	100	100
UNIT B37	1,000 SF	A-2	100	100
UNIT B38	1,000 SF	A-2	100	100
UNIT B39	1,000 SF	A-2	100	100
UNIT B40	1,000 SF	A-2	100	100
UNIT B41	1,000 SF	A-2	100	100
UNIT B42	1,000 SF	A-2	100	100
UNIT B43	1,000 SF	A-2	100	100
UNIT B44	1,000 SF	A-2	100	100
UNIT B45	1,000 SF	A-2	100	100
UNIT B46	1,000 SF	A-2	100	100
UNIT B47	1,000 SF	A-2	100	100
UNIT B48	1,000 SF	A-2	100	100
UNIT B49	1,000 SF	A-2	100	100
UNIT B50	1,000 SF	A-2	100	100
UNIT B51	1,000 SF	A-2	100	100
UNIT B52	1,000 SF	A-2	100	100
UNIT B53	1,000 SF	A-2	100	100
UNIT B54	1,000 SF	A-2	100	100
UNIT B55	1,000 SF	A-2	100	100
UNIT B56	1,000 SF	A-2	100	100
UNIT B57	1,000 SF	A-2	100	100
UNIT B58	1,000 SF	A-2	100	100
UNIT B59	1,000 SF	A-2	100	100
UNIT B60	1,000 SF	A-2	100	100
UNIT B61	1,000 SF	A-2	100	100
UNIT B62	1,000 SF	A-2	100	100
UNIT B63	1,000 SF	A-2	100	100
UNIT B64	1,000 SF	A-2	100	100
UNIT B65	1,000 SF	A-2	100	100
UNIT B66	1,000 SF	A-2	100	100
UNIT B67	1,000 SF	A-2	100	100
UNIT B68	1,000 SF	A-2	100	100
UNIT B69	1,000 SF	A-2	100	100
UNIT B70	1,000 SF	A-2	100	100
UNIT B71	1,000 SF	A-2	100	100
UNIT B72	1,000 SF	A-2	100	100
UNIT B73	1,000 SF	A-2	100	100
UNIT B74	1,000 SF	A-2	100	100
UNIT B75	1,000 SF	A-2	100	100
UNIT B76	1,000 SF	A-2	100	100
UNIT B77	1,000 SF	A-2	100	100
UNIT B78	1,000 SF	A-2	100	100
UNIT B79	1,000 SF	A-2	100	100
UNIT B80	1,000 SF	A-2	100	100
UNIT B81	1,000 SF	A-2	100	100
UNIT B82	1,000 SF	A-2	100	100
UNIT B83	1,000 SF	A-2	100	100
UNIT B84	1,000 SF	A-2	100	100
UNIT B85	1,000 SF	A-2	100	100
UNIT B86	1,000 SF	A-2	100	100
UNIT B87	1,000 SF	A-2	100	100
UNIT B88	1,000 SF	A-2	100	100
UNIT B89	1,000 SF	A-2	100	100
UNIT B90	1,000 SF	A-2	100	100
UNIT B91	1,000 SF	A-2	100	100
UNIT B92	1,000 SF	A-2	100	100
UNIT B93	1,000 SF	A-2	100	100
UNIT B94	1,000 SF	A-2	100	100
UNIT B95	1,000 SF	A-2	100	100
UNIT B96	1,000 SF	A-2	100	100
UNIT B97	1,000 SF	A-2	100	100
UNIT B98	1,000 SF	A-2	100	100
UNIT B99	1,000 SF	A-2	100	100
UNIT B100	1,000 SF	A-2	100	100

1 1ST FLOOR
300' x 150'

OCCUPANCY CLASSIFICATION

- ☐ A-2
- ☐ A-3
- ☐ B
- ☐ I-1
- ☐ S-1


NOTE: ACCESSIBLE MEANS OF EGRESS THROUGH STAIRS AND ELEVATORS



OCCUPANCY TABULATION - 2ND FL

NAME	AREA	CLASSIFICATION	UNIT	TOTAL
STAIRS	141 SF	B	Staircase (Unoccupied)	141
OFFICES	141 SF	A-2	Offices (Unoccupied)	141
RECEPTION	141 SF	A-2	Reception (Unoccupied)	141
OUTDOOR TERRACE	141 SF	A-2	Outdoor Terrace (Unoccupied)	141
RESTROOMS	141 SF	A-2	Restrooms (Unoccupied)	141
STORAGE	141 SF	A-2	Storage (Unoccupied)	141
MECHANICAL	141 SF	A-2	Mechanical (Unoccupied)	141
LANDSCAPE	141 SF	A-2	Landscape (Unoccupied)	141
RESIDENTS	141 SF	A-2	Residents (Unoccupied)	141


GENERAL SITE NOTES
SEE SHEET A102 FOR TREE RETENTION PLAN
SEE SHEET A103 FOR CRITICAL AREA DESCRIPTION



2015 LB C. GRADE PLANE CALCULATION
 FOR BASEMENT QUALIFICATIONS:

SEGMENT	START	END	AVG ELEV	LENGTH	ELEV LENGTH
A	337.9'	330.3'	334.1'	91.4'	30536.74'
B	330.3'	331.0'	330.7'	63.0'	20850.55'
C	331.0'	331.0'	331.0'	5.1'	3022.10'
D	331.0'	335.6'	334.6'	22.7'	7651.85'
E	335.6'	343.0'	339.3'	33.8'	11500.25'
G1	343.0'	343.0'	343.7'	33.8'	11690.24'
G2	343.0'	343.0'	343.0'	16.8'	5762.40'
G3	343.0'	330.3'	336.7'	33.8'	11378.77'
I	343.0'	343.0'	343.7'	108.9'	37367.14'
J	343.0'	342.7'	342.9'	4.1'	1405.69'
M1	343.0'	340.3'	342.7'	30.2'	10548.03'
M2	342.7'	337.9'	340.3'	11.8'	4015.54'
			4059.0'	473.2'	159916.10'

Grade Plane Elevation: 337.97'



1 SITE - AVERAGE GRADE PLANE
 1" = 100'

TREES IN REQUIRED TRANSITION BUFFER:
ALL TREES WITHIN 10' OF PROPERTY LINE TO REMAIN
PER 2023B (M)(C) (2)(b)



- EXISTING VISIBLE TREE TO REMAIN
- EXISTING VISIBLE TREE TO BE REMOVED
- EXISTING NON-VISIBLE TREE TO REMAIN
- EXISTING NON-VISIBLE TREE TO BE REMOVED

SEE ARBORIST'S REPORT FOR DETAILED DESCRIPTION

TREES OUTSIDE OF REQUIRED BUFFER:
15% OF CALIPER INCHES OF SIGNIFICANT TREES
PER BMC 20.20.900 D(2)(a) & BMC 20.25.40 C(2)(b)

TREE	ADJUSTED VALUE
1405	15"
1406	16"
1407	18"
1408	24"
1409	45"
1410	35"
1411	7"
1412	6"
1413	110"
TOTAL	237"

TREE	ADJUSTED VALUE
1401	31"
1402	31"
1403	18"
1404	13"
1405	23"
1406	23"
1407	15"
1408	14"
1409	8"
1410	10"
1411	10"
1412	23"
1413	137"
TOTAL	407"


TOTAL VALUE OF INTERIOR TREES = 407
TOTAL VALUE OF NON-INTERIOR TREES = 201
TOTAL RETAINED VALUE = 170
PERCENT RETAINED = 85% > 15%


TREES - TOTAL SITE:
25% OF CALIPER INCHES OF SIGNIFICANT TREES

TREE	ADJUSTED VALUE
1405	15"
1406	16"
1407	18"
1408	24"
1409	45"
1410	35"
1411	7"
1412	6"
1413	110"
TOTAL	237"

TREE	ADJUSTED VALUE
1401	31"
1402	31"
1403	18"
1404	13"
1405	23"
1406	23"
1407	15"
1408	14"
1409	8"
1410	10"
1411	10"
1412	23"
1413	137"
TOTAL	407"


TOTAL VALUE OF ON-SITE TREES = 477
TOTAL NON-VISIBLE DBH = 309
TOTAL VISIBLE DBH = 168
TOTAL RETAINED VALUE = 137
PERCENT RETAINED = 82% > 25%





BACKSIGHT ALLOWED = 15 x 100 ACRES = 12
DENSITY ADJUSTED FOR CRITICAL AREA AND BUFFER
DENSITY CALCULATION
CRITICAL AREA = 1,424 SF
TOTAL = 9,022 SF = 25.84
150,000 sq ft / 25.84 = 5,805 sq ft / acre = 58.05 acres
150,000 sq ft / 58.05 acres = 2,584 sq ft / acre = 25.84 acres
100,000 sq ft / 25.84 acres = 3,870 sq ft / acre = 38.70 acres
PROPOSED = 32 SLEEPING UNITS (107 sq ft)






SILVERADO BELLEVUE


14341 SE 16th STREET

BASEMENT FLOOR PLAN



WATTS & ASSOCIATES, INC.





ELEVATION KEYNOTES

MATERIALS:	01	02	03	04	05	06	07
	Architectural Concrete neutral black, with wood panel	Admixed Manufactured Stone Veneer Colonial Stone Landscape for Stone	Flare Cement Lap Siding, 6" exposure applied randomly by approved sub	Flare Cement Panel Siding w/ aluminum Channel Reveal system applied randomly by approved sub	Flare Cement Accent Cladding, natural wood appearance, applied 4" x 6" exposure Weathering Ridge, 1/2" x 3" Weathering Ridge	Vinyl Window, White	Asphalt Shingle Asphalt Shingle Contingent - Presidential Solaris, Weathered Wood


PANT COLORS:	A	B	C
	Light Body Color: Medium Gray SW 7032	Medium Body Color: Smokehouse SW 7040	Trim Color: Linen Bronze SW 7048



1 EXTERIOR ELEVATION - NORTH
1/8" = 1'-0"



2 EXTERIOR ELEVATION - NORTHWEST
1/8" = 1'-0"




3 EXTERIOR ELEVATION - SOUTHWEST
1/8" = 1'-0"

ELEVATION KEYNOTES

MATERIALS:	PAINT COLORS:
01 Architectural Concrete	A Light Body Color, Medium Gray SW 7032
02 Asphered Manufactured Stone Veneer, 3/4" thick, 12" x 12" x 8" deep, 35% light	B Medium Body Color, Smokehouse SW 7040
03 Fiber Cement Siding, 1/2" thick, 12" x 12" x 8" deep, 35% light	C Tree Color, Urnsa Bronze SW 7048
04 Fiber Cement Panel Siding w/ aluminum system, 1/2" thick, 12" x 12" x 8" deep, 35% light	
05 Fiber Cement Accent Cladding, natural wood grain, alternating 4" x 8" & 8" x 8" rectangles	
06 Vinyl Window, White	
07 Asphalt Shingle Roofing, Cedarshake - Presidential Solars, Weathered Wood	



1 EXTERIOR ELEVATION - SOUTH
1/8" = 1'-0"



2 EXTERIOR ELEVATION - SOUTHEAST
1/8" = 1'-0"



3 EXTERIOR ELEVATION - NORTHEAST
1/8" = 1'-0"




SILVERADO BELLEVUE
14341 SE 16th STREET

BIRD'S EYE
PERSPECTIVES







- TREES IN REQUIRED TRANSITION BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)
- = EXISTING VISIBLE TREE TO REMAIN
 - ⊗ = EXISTING VISIBLE TREE TO BE REMOVED
 - ⊗ = EXISTING NON-VISIBLE TREE TO REMAIN
 - ⊗ = EXISTING NON-VISIBLE TREE TO BE REMOVED
- SITE INTERIOR:**
SEE ARBORISTS REPORT FOR DETAILED DESCRIPTION
- TREES OUTSIDE OF REQUIRED BUFFER
15% OF CALIPER INCHES OF SIGNIFICANT TREES PER BMC 20.20.000 (2)(g) & BMC 20.25.40 (2)(b)

TREE	ADJUSTED VALUE
1405	19"
1406	16"
1407	18"
1408	24"
1409	45"
1410	35"
1411	7"
1412	5"
1413	110"
TOTAL	
REMOVED:	
1401	31"
1402	31"
1403	18"
1404	18"
1405	19"
1406	16"
1407	18"
1408	24"
1409	45"
1410	35"
1411	7"
1412	5"
1413	110"
TOTAL	

TOTAL VALUE OF INTERIOR TREES = 407
TOTAL VALUE OF BUFFER TREES = 170
TOTAL RETAINED VALUE = 170
PERCENT RETAINED = 85% > 15%

TREES - TOTAL SITE:
25% OF CALIPER INCHES OF SIGNIFICANT TREES

TREE	ADJUSTED VALUE
1405	19"
1406	16"
1407	18"
1408	24"
1409	45"
1410	35"
1411	7"
1412	5"
1413	110"
TOTAL	
REMOVED:	
1401	31"
1402	31"
1403	18"
1404	18"
1405	19"
1406	16"
1407	18"
1408	24"
1409	45"
1410	35"
1411	7"
1412	5"
1413	110"
TOTAL	

TOTAL VALUE OF ONSITE TREES = 477
TOTAL NON-VISIBLE DBH = 309
TOTAL VISIBLE DBH = 168
TOTAL RETAINED VALUE = 137
PERCENT RETAINED = 82% > 25%

543.12' N88°49'02"W 174.80' N1°41'29"E 136.23' N68°03'45"E 93.20' N22°12'23"W 122.73' N67°47'37"E 1.53' N22°13'03"W

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)


TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)

TREES IN BUFFER ARE TO BE REMOVED. PROPERTY LINE TO REMAIN PER 20.238.04(1)(c) (2)(b)



LEGEND:

⊗ NEW BOLLARD LIGHT

INDICATES SIGHT DISTANCE FROM POINT A TO POINT C, REFER TO SIGHT DISTANCE EXHIBIT PREPARED BY PACE ENGINEERING.

SOIL PREPARATION FOR LANDSCAPE STRIPS

City of Bellevue

DATE: 09/06/23
SCALE: 1" = 10'-0"
DESIGNER: ACE
CHECKED: JMA

NO.	REVISION	DATE	BY	CHKD.
1	ISSUED FOR PERMIT	09/06/23	JMA	ACE

PLANTING PLAN

SILVERADO BELLEVUE

14641 SE 16th STREET
 SILVERADO SENIOR LIVING



JCM:ND

PL OT DATT

DATE: 09/06/23
 SCALE: 1" = 10'-0"
 DESIGN: ACE
 CHECKED: JMA































SHEET NO.

L1.1



IN ANTIQUE FINISH
 1" = 10'-0"

PLANT PALETTE - PROJECT SITE

SYMBOL	BOTANICAL / COMMON PLANT NAME	SIZE	QTY	REMARKS
* 	ACER ORIENTALIS / JAPANESE MAPLE	8' H 12' DIA	10	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	ACER PLATANIFOLIA / NORWAY MAPLE	2' CAL	5	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'
* 	PROSTRA PTERIS / WAXY	2' CAL	1	10' DIA @ 10' DIA, 1' DIA @ 10'

NOTES:
E: EVERGREEN
D: DECIDUOUS

PLANT QUANTITIES SHOWN ON PLANT PALETTE ARE FOR CONTRACTOR CONVENIENCE ONLY. CONTRACTOR SHALL VERIFY QUANTITIES PRIOR TO SUBMITTING BIDS.

* INDICATES NATIVE PLANT MATERIAL

